

# CONCRETE AND CONSTRUCTIONAL ENGINEERING

AUGUST, 1951.



Vol. XLVI, No. 8

FORTY-SIXTH YEAR OF PUBLICATION

PRICE 1s. 6d.

ANNUAL SUBSCRIPTION 18s., POST FREE. \$3.99 in Canada and U.S.A.

## LEADING CONTENTS

	PAGE
Scarcities . . . . .	231
Wharf and Tunnels at Electricity Works . . . . .	233
Bending Moments due to Temperature Changes in Continuous Reinforced Concrete Structures. <i>By A. Chronowicz</i> . . . . .	241
Residential Flats in South London . . . . .	253
A Prestressed Concrete Lighthouse . . . . .	257

No. 525.

ISSUED MONTHLY

Registered for  
Canadian Magazine Post

## BOOKS ON CONCRETE

For catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:  
CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., WESTMINSTER, S.W.1



*For over 60 years*

this trade mark has stood for speed and  
strength in reinforced concrete work.

# DRAGON

(Brand)

## PORTLAND CEMENT

*Supplied by*

THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.  
PENARTH, SOUTH WALES

Telephone : Penarth 300

Telegrams : "Cement, Penarth"

# Burton's

(SAFETY LOCK—UNIQUE FEATURE)

## TUBULAR STEEL PROPS

(ADJUSTABLE)

*For Supporting Temporary Floor Shuttering*

### Burton's Adjustable Tubular Steel Props

for the above and many other purposes, are much preferred by the men who erect them to the old-fashioned Timber Props. They can be erected by one man in a few minutes and positively adjusted and **safely locked** in position, thus avoiding any possibility of being accidentally or maliciously tampered with.

*Manufactured in our own most modern and up-to-date works at Old Hill, Staffs.*

No spanner, jack, or tommy bar necessary; simply lift inner tube, insert peg, and tighten up.

*No loose parts to lose, and easily transported.*

### BURTON'S ADJUSTABLE TUBULAR STEEL BEAM PROPS

are provided, as illustrated, with a braced head for supporting temporary shuttering to R.S.J. casings and reinforced concrete beams, &c.



Size No.	HEIGHT		Approx. Weight each in Lb.
	Fully Closed	Fully Extended	
1.	5 ft. 7 in.	9 ft. 10 in.	50
2.	6 ft. 7 in.	10 ft. 10 in.	54
3.	8 ft. 2½ in.	12 ft. 5½ in.	58
4.	11 ft. 0 in.	16 ft. 0 in.	72

*Head Fittings to suit any Special Job, designed for use with BURTON'S PROPS.*

## Burton's Patent Solid Dropforged Steel Scaffolding Fittings

## THE LONDON & MIDLAND STEEL SCAFFOLDING CO., LTD.

ST. LUKE'S WORKS, OLD HILL, STAFFORDSHIRE

Telegrams : DUBELGRIP, CRADLEY HEATH.


Telephone : CRADLEY HEATH 6237/8

London Offices : BURWOOD HOUSE, CAXTON STREET, S.W.1

Telephone : Abbey 6483/4

Telegrams : Dubelgrip, Sowest, London

# the new improved electric vibrator



**EXCEPTIONALLY LOW  
MAINTENANCE COSTS**

**HIGH SPEED  
LONG LIFE**

This easily operated electric internal vibrator, with its new features for increased efficiency in vibrating harsh and dry concrete, provides the means of cutting vibrating costs to a minimum. It will stand up to the hardest wear and tear under the most severe working conditions with maintenance costs that are practically negligible. The motor is fully protected, and works on 110 volts, single phase A.C., or 110 volts D.C.; alternatively on 230 volts, single phase A.C., or 230 volts D.C. supply. Vibrating heads are supplied in three interchangeable sizes. Free working demonstrations will be arranged without obligation on application to:

## COMPACTORS ENGINEERING LTD

ALSO SUPPLIERS OF PNEUMATIC IMMERSION VIBRATORS  
VIBROSOIL COMPACTORS : TRENCH COMPACTORS  
S.G.M.E. VIBRO-FINISHERS, JOINT CUTTERS AND DISTRIBUTORS  
HYDRAULIC BAR CROPPERS AND

### BAR BENDERS

We can give early delivery of bar-benders. Speedy and accurate, these machines are strongly constructed for long life with low maintenance costs. Let us send you full details.

1A BRAILSFORD ROAD, LONDON, S.W.2.

TELEPHONE : TULSE HILL 1131-2





*Concrete pumped by pipeline*


### **Heavy Foundations for Cold Reduction Mill at Abbey Works for the Steel Company of Wales Limited**

*Consulting Engineers: W. S. Atkins & Partners*

The Cold Reduction Mill is one of the large steel processing elements in Britain's major steel-works project for the Steel Company of Wales Limited, at Abbey Works, opened on 17th July by The Rt. Hon. Hugh Gaitskell C.B.E., M.P., Chancellor of the Exchequer.

**LAING**

Contractors for every class of Building and Civil Engineering work at home and overseas  
*John Laing and Son Limited, London, Carlisle, Johannesburg, Lusaka. Established in 1848*



*Fixing steel reinforcement*


# POWER BAR BENDERS

## FOR ALL SIZES OF REINFORCING BARS


### STANDARD PRODUCTION MODELS

The ARD. 50 MODEL—as illustrated on right—has a capacity for cold bending Mild Steel Bars up to 2" dia. and incorporates a second Bending Head to give high-rate bending for small diameter bars.

The RAS. 40 MODEL shown below is a single disc machine of exceptional performance. With a capacity for 1½" dia. bars, it bends at highest practical rate—e.g. a full hook takes only 3 seconds bending time.



*Ensure accuracy, economy  
& simplicity of operation*



### INTERESTING FEATURES

Either of the Models illustrated can be supplied motorised or engine driven.

Standard Accessories supplied include all necessary Formers and Bending Pins, a special Backrest for simultaneous bending of a number of small diameter bars, and Accessories for forming right-angle loops in one operation.

Special Safety Device incorporated to prevent damage to mechanism if overloaded.

The desired Bending Angle may be set mathematically, and this is of great assistance in Repetition Bending.

# CEMENT & STEEL LTD.

SECOND AVENUE

CHATHAM

KENT

Telephone: Chatham 45580

Telegrams and Cables: Cembelgi, Chatham



*Photo. by kind permission of the Ministry of Civil Aviation. Contractors: George Wimpey & Co. Ltd.*

## ***London Airport takes to SISALKRAFT***

The illustration depicts the experimental length of *prestressed concrete taxi track* recently undertaken by the Ministry of Civil Aviation at London Airport.

After the formation had been suitably compacted a 2" bed of sand was spread over the paved area and SISALKRAFT Reinforced Waterproof Building Paper (Standard grade) utilised to ensure that the precast slabs had complete freedom of movement, both during and after stressing of the cables. Indeed a function to test even the performance of SISALKRAFT.

Such Structures Suggest

**SISALKRAFT**  
TRADE MARK

The Building Paper

Sole Distributors for British  
Sisalkraft Limited

**J.H. SANKEY & SON. LTD**

ALDWYCH HOUSE, ALDWYCH, LONDON, W.C.2. Telephone: Holborn 6949. Telegrams: Brickwork, Estrand, London


## *take it up with Wickham*

WICKHAM Builders' Hoists, all models, include quick fitting Tower Masts which take substantially less time to erect. The Mast sections are designed to butt on to each other and so rabbeted as to be automatically self-aligning. Sections are held together by six bolts only, no fish plates being required. The Power unit is totally enclosed in a steel housing affording complete protection. All Wickham Friction Winches are fitted with self-aligning ball and/or roller bearings, giving longer life and lower maintenance costs. All Wickham Builders' Hoists are fitted with an Automatic platform control which increases the life of the wire bond and prevents crashed platforms.

Leading Contractors on the Festival of Britain sites made extensive use of WICKHAM BUILDERS' HOISTS

### WICKHAM PRODUCTS

Builders' Hoists (Mobile and Static), Passenger Hoists, Concrete Elevators, Diaphragm Pumps, Power Winches, Portable Winches, Brick Barrows, Safety Gates



*Please write to us for interesting literature and the name of our agent in your area.*

TAKE IT  UP WITH


# *Wickham*

WICKHAM  
ENGINEERING CO. LTD.

(Dept. 4) 34 VICTORIA ST., LONDON, S.W.1. Phone: ABBEY 5967-8  
Grams: Wicamite Sowest London

# MILFORMS

**FOR AUTOMATIC ALIGNING AND  
SELF-SUPPORTING SHUTTERING TO  
WALLS, FLOORS, COLUMNS AND BEAMS, ETC.**



*Inspection of the actual plant will show the simple and robust nature of the equipment which has been designed for rapid fixing and easy maintenance.*

**This new range of formwork, for use on all types and systems of concrete construction, provides the Contractor with the means of overcoming formwork difficulties in an easy and economical way. No special tools are required, it is easy to erect and dismantle, and robustly constructed to withstand heavy wear. Full information can be obtained from any Mills Depot.**


**MILLS**  
**SCAFFOLD CO., LTD.**

BELFAST • BIRMINGHAM • BOURNEMOUTH • BRIGHTON • BRISTOL  
CANTERBURY • CARDIFF • COVENTRY • CROYDON • DUBLIN  
EXETER • GLASGOW • HULL • ILFORD • LIVERPOOL • LOWESTOFT  
MANCHESTER • NEWCASTLE • NORWICH • PLYMOUTH  
PORTSMOUTH • SOUTHAMPTON • SWANSEA • YARMOUTH

Head Office & Depot: TRUSSLEY WORKS, HAMMERSMITH GROVE, LONDON, W.6. Tel: RIVerside 5026/9

# BRC


brings the accuracy of  
the drawing board to the job



Issued by **THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD**  
*Specialists in Reinforced Concrete Design & Suppliers of Reinforcement*  
London, Birmingham, Bristol, Leeds, Leicester, Manchester, Newcastle, Sheffield, Cardiff, Glasgow, Dublin, Belfast







All the concrete on this superstructure was placed with one ACE hoist. Whatever you are building—a power station, factories, offices, flats or houses, your choice of plant is most important. But most important of all is the hoisting equipment, the pacemaker of the job. And that's where we come in. The ACE range of electric, petrol or diesel-driven hoists includes those with hoisting speeds up to 250 ft. per minute, 5/50 cwt. Platform Hoists, Concrete Elevating Plants, Workmen/Goods Hoists, Mobile Platform Hoists, Tunnel Hoists, Shaft Hoists, Transporters, Haulage Winches. Lightweight Portable Winches for hoisting reinforcing bars, etc.

FOR ALL TYPES OF BUILDING CONSTRUCTION

use

**ACE**

PLATFORM HOISTS WINCHES

hoists

**Sale or Hire**



A.C.E. MACHINERY LTD., Porden Road, Brixton, London, S.W.2  
and at Brentford.

Telephone: Brixton 3293 (9 lines)

**SIR ROBERT**  
**McALPINE**  
**& SONS LTD**

**CONTRACTORS**  
**FOR**  
**BANKSIDE**  
**POWER STATION**

This contract includes the construction of a Power House, River Wharf, Storage Tanks, Tunnels under the River Thames, and the supply of reinforced concrete segments

# GUNITE AND CEMENTATION



Systematic repairs to structures  
based on systematic diagnosis of  
defects.


## WHITLEY MORAN & CO. LTD.

*Specialists In the Repair of Engineering Structures*

5 OLD HALL STREET, LIVERPOOL.

Telephone: Central 7975

# "CAPCO" H. F. VIBRATOR



for compacting mortar cubes  
for Compression Test B.S.  
12/1947, B.S. 915/1947,  
B.S. 146/1947, B.S.  
1370/1947 with automatic  
time control device. The  
vibrator illustrated in the  
B.S. was built in our works.

The "CAPCO" range of con-  
crete testing apparatus also  
includes Cube Moulds; Slump  
Cones; Tensile, Vicat, and Cylin-  
drical Moulds; Tile Abrasion  
Machines; Compacting Factor  
Apparatus.

Full details on request.

## CAPCO (SALES), LTD.

(Sole Agents for all  
"Capco" Products)

BEACONSFIELD ROAD, LONDON, N.W.10. Telephone: WILLEDEN 9867-3. Cables: CAPLINKO, LONDON

## 17 FT. CANTILEVER SLABS IN PRESTRESSED CONCRETE

THE SWORD EXHIBITED AT  
THE MAIN ENTRANCE OF THE  
BUILDING WEEK EXHIBITION  
LEEDS 1950

demonstrates some of the outstanding qualities of prestressed concrete. The concrete was made in short sections, assembled with dry joints, and prestressed on the site. The hilt and blade of the sword, standing 50 ft. high, are prestressed by three  $\frac{3}{4}$ " diameter 'MACALLOY' Steel Bars.

The handguard is of special interest. Comprising two cantilevers 17 ft. long, with an overall wing span of 36 ft., it is designed to sustain point loads of 400 lb. at the tips. The cross-section of each wing measures 24"  $\times$  6" at the root, tapering to 3" deep at the tip. The cantilevers are prestressed with four  $\frac{3}{4}$ " diameter 'MACALLOY' Steel Bars. The total weight of bars in the complete structure is 560 lb. Lee-McCall fittings and prestressing equipment were used throughout.



made of prestressed concrete  
BY THE  
**LEE-McCALL SYSTEM**

**McCALL AND COMPANY (SHEFFIELD) LIMITED**  
TEMPLEBOROUGH, SHEFFIELD AND AT LONDON

# SUPER CEMENT

**'SUBMARINE' BRAND**

THE TANNO-CATALYSED PORTLAND CEMENT

**SAVES TIME**

**SAVES TROUBLE**

NATURALLY WATERPROOF. CONTAINS NO WATER REPELLENT MATERIAL

Uses:—

**For CONCRETE**

Provides a CONCRETE of great strength at early dates and impervious to water, oil, etc., without any form of surface coating.

**For PAVING**

Produces a hard wearing PAVING, dustless and proof against penetration by water, etc.

**For RENDERING**

Supplies an impenetrable RENDERING of such adhesive power that a 1" thickness will resist an outside pressure of at least a 20' head of water.

**For SLURRY (as paint)**

Makes a perfectly watertight covering to brick or breeze concrete walls at very small cost, and also provides the best watertight undercoat to coloured finishes.

Technical Information is available to users.

Used in 1914-1918 and still used by:

Air Ministry, War Office, Admiralty, Ministry of Works, Ministry of Supply, etc.

**SUPER CEMENT LTD.,**

29 TAVISTOCK SQUARE, Phone 1  
LONDON, W.C.1 Euston 1808



**PIN YOUR FAITH  
TO THE TESTED  
BRAND.**

THIS LABEL ON  
EVERY BARREL  
CARRIES WITH IT  
FORTY YEARS'  
EXPERIENCE OF  
MANUFACTURE.

**NONE OTHER IS  
"JUST AS GOOD"**


**THE LEEDS OIL & GREASE CO.**

'Phone: 22480.

**LEEDS**


'Grams: "Grease."





Reinforced Concrete Building constructed for  
**HUMPHREYS & GLASGOW LTD.**  
at the  
NORTH THAMES GAS BOARD'S BECKTON WORKS

**PETER LIND & CO LTD**  
STRATTON HOUSE, PICCADILLY, W.1



An Electrically Driven PC4 Concrete Pump.  
Capacities from 8 to 10 cu. yds. per hour.  
Ranges actually obtained 125 ft. vertical or  
1,500 ft. horizontal.

## CONCRETE BY PUMP AND PIPELINE

- The latest and most efficient method of placing concrete.
- Pump and Mixing plant can be located where it is most convenient for storing and handling aggregates and cement.
- The concrete is delivered by pipeline just wherever it is required with the minimum of interference with the building operations.
- The speed of the pump governs the whole of the concreting gang.
- Pumpable concrete must of necessity be good concrete.

### THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8


Telephone: Western 3546.

Telegrams: Pumpcret, Kens, London.

# DOUGLAS

RIVERSLEY PARK

NUNEATON



G. ASHTON, A.M.I.C.E., M.I.Mun.E.,  
*Borough Engineer.*

MAGNEL-BLATON EQUIPMENT  
SUPPLIED BY  
STRESSED CONCRETE DESIGN, LTD.

**first prestressed bridge  
in the Midlands  
SPAN 60 ft.**

ROBERT M. DOUGLAS (CONTRACTORS) LTD.

395 GEORGE RD., BIRMINGHAM, 23. AND BRIDGE RD., WAUNARLWYDD, nr. SWANSEA.

# CONCRETE P ROOFING Co. LTD.

# GUNITE SPECIALISTS

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request.


100, Victoria Street, Westminster, S.W.1

Telephone:  
VICTORIA 7877 and 8376

## KEEPING CORROSION AWAY ....


Industrial floors have to be designed to resist the most violently corrosive processes. The illustration shows a five-layer floor of Windsor's materials, scientifically planned to give maximum protection. Windsor's produce a complete range of materials and preparations for proofing concrete and resisting corrosion. Their methods of carefully planned floor laying ensure a liquid-tight and acid-, alkali- or oil-resisting surface which will give years of service without repair.

Details and advice on any problem are gladly given.



## H. WINDSOR & CO. LTD.

748 FULHAM ROAD, S.W.6. Telephone: RENown 6006/7/8  
119 VICTORIA STREET, S.W.1. Telephone: VICtoria 9331/2



Elimination  
of Level Crossings,  
Loughlin Branch—Essex.  
George Lane Viaduct, & Woodford.  
County Surveyor: H. J. Berry, Esq., M.I.C.E.  
M.I.Mun.E.  
Consulting Engineers: Rendel,  
Palmer & Tritton.

**HEAD OFFICE**

50 Epping New Road,  
Buckhurst Hill, Essex.  
Tel: Buckhurst 4444  
(13 lines).

**LONDON OFFICE**

47 Victoria Street,  
Westminster, S.W.1.

**BRANCH OFFICES**

**ROMFORD**

217 Brentwood Road,  
Romford.

Tel: Romford 2828.

**WISBECH**

South Brink, Wisbech  
Tel: Wisbech 1530.

**COLCHESTER**

Ipswich Road, Dedham,  
Nr. Colchester.  
Tel: Dedham 3133.

**KENYA**

P.O. Box 651, Nairobi,  
Kenya.

**BRICKFIELDS AT**

Chigwell Rd.,

S. Woodford, E.18.

Tel: Buckhurst 1276,

Luxborough Lane,

Chigwell.

Tel: Buckhurst 5033.

Ongar, Essex.

Tel: Ongar 48.

Makers of Stock Bricks,

Facing Bricks, Roof

Tiles, Land Drains, and

other clay products.

**TRANSPORT &**

**PRECAST CON-**

**CRETE DEPT.**

North Farm.

Loughton, Essex.

Tel: Loughton 480.

Lighterage and Wharf-

age facilities on River

Lea.

**CONTRACTORS**

**FOR:**

Air Ministry, London

County Council,

Railway Executive

British Railways,

Catchment Boards,

London Transport

Executive, Colne

Valley Sewerage Board,


Middlesex County

Council,

East Middlesex Main

Drainage, and other

Authorities



W & C  
**FRENCH**  
LTD

*Contractors for civil engineering works*

# MOULD OILS & COMPOUNDS

for every process of  
concrete production

## CONCREAM

This non-staining, smooth and easy working white mould oil can be used with confidence on all classes of in situ and precast concrete work where the use of a white mould oil is recommended.

## VIBRAMOL

This non-staining and non-separating mould oil is made specially for use on steel shuttering and moulds where vibrators are used, and provides a good film which is not readily moved under vibration.

## SPRAYMOL

This grade of mould oil has been specially produced for use with a spray gun. It can be used with great economy on all types of shuttering and moulds, and will not separate under pressure.

## "P.S."

Experience has shown that the production of precast and in situ prestressed concrete needs a special mould compound, and in collaboration with leading prestressed specialists we have produced Grade "P.S." Mould Compound for this class of work.

## "8.A."

This Mould Compound has been specially produced to satisfy the requirements of those engaged in the production of spun concrete products.

**CONCREAM** Regd.  
**VIBRAMOL** Regd.  
**SPRAYMOL** Regd.  
**"P.S." & "8.A."**

PRODUCTS OF THE  
ORIGINAL MAKERS OF  
CONCRETE MOULD OILS

We specialise in the production of mould oils and compounds for concrete work of every kind, from mass concrete work to high-class architectural stone work, and have an unrivalled experience which enables us to give expert advice on all mould oil problems. We have a grade for every purpose, and will be pleased to submit full details, samples, and prices on request.

**RICH<sup>d</sup> HUMBLE & SON, LTD., COLUMBA OIL WORKS, LEEDS, 3**

Telephone : 27155.

ESTABLISHED 1854.

Telegrams : "Columba, Leeds, 3."





Nine-story and seven-story flats constructed by us in reinforced concrete for the Wandsworth Borough Council on the Notre Dame Estate.

*Architects : Messrs. James and Bywaters.*

*Consulting Civil Engineers : Messrs. R. T. James & Partners.*

# **WILLIAM MOSS & SONS LTD**

**Building and  
Public  
Works Contractors**

**LONDON**

**LOUGHBOROUGH**

**LIVERPOOL**

## "CRETE-O-LUX" WINDOWS


at  
Ocean Dock Terminal  
SOUTHAMPTON



# HAYWARDS

## "CRETE-O-LUX" LIGHTS

Haywards manufacture an important range of Building Specialities. Particulars gladly sent on request.




Haywards "Crete-o-Lux" Lights, of reinforced concrete construction, are purpose-made and precast (unless otherwise required) for maximum efficiency and dependability. These Lights meet every need of present-day practice, being specially designed for Pavements, Roadways, Floors, Stallboards, Roofs, Domes, Canopies, Lanterns, Windows, etc. Their use ensures good appearance and the best possible transmission of light.

WATerloo 6035-6039

**HAYWARDS LTD., UNION ST., LONDON, S.E.1**

# **CHRISTIANI & NIELSEN LTD**


## **REINFORCED CONCRETE**



**54 VICTORIA STREET,**


**LONDON, S.W.1**

TELEPHONE: VICTORIA 6152



# KWI

The above photograph effectively demonstrates the ease of erection of Kwikform Unit-Frame Scaffolding—striking is just as simple



KWIKFORM LTD., WATERLOO ROAD, B

# KWIKFORM

## ... the Unit-Frame Scaffolding System ...

has revolutionised all previous conceptions of scaffolding. Economies obtained from its use have been officially acknowledged by Government authorities as well as by all sections of the Building and Civil Engineering Industries. Fully descriptive literature is available on application.



The twist-core collet provides for rapid adjustment to fine limits on the **ADJUSTABLE BASE**. It was only by this ingenious 'Kwikform' invention that the scaffolding problems of the building industry could be brought within the scope of full-scale factory prefabrication with all its benefits.


**All Kwikform Scaffolding is available for hire or purchase.**

Patents granted or pending in all Principal Countries of the World.

('KWIKFORM' is the registered trade name of KWIKFORM LTD.)

The Illustration below of Nchells Power Station, which is reproduced by permission of the British Electricity Authority, shows the application of our Unit-Frame System to external and internal large-scale constructional operations.

Illustrated below is the adaptability of our Unit-Frame System to extremely difficult site conditions.



MANCHESTER 25.

London Office: 66, Victoria Street, S.W.1

L.G.B.



*Ferro-Concrete Bars on the Cooling Bed of the new Merchant Bar and Wire Rod Mill at Dalzell Steel Works.*

The large tonnage produced in this Mill provides an opportunity to

**FERRO CONCRETE CONTRACTORS**

of obtaining prompt and efficient service of highest quality


**REINFORCING BARS**

Mild and High Tensile Steel in round or square section.

**PLAIN or INDENTED**

$\frac{1}{4}$ " and upwards in coils, straight lengths or hooked and bent ready for assembly.

**COLVILLES**



**STEELS**

will serve you well


COLVILLES LTD 195 WEST GEORGE STREET GLASGOW C2



# Ellispun

## concrete pipes

for the piers of  
the river wharf  
at Bankside  
Power Station



Consulting Engineers to the British Electricity Authority: Messrs. Mott, Hay and Anderson.  
Contractors: Sir Robert McAlpine & Sons, Ltd.

The eight pairs of piers for this wharf are constructed of spun reinforced concrete pipes in 6-ft. rings of 6 ft. 8 in. outside diameter, and filled with concrete. These pipes were manufactured by—

**JOHN ELLIS & SONS LIMITED**

21 NEW WALK, LEICESTER

Phone: Leic. 5682 (7 lines)

SOLE AGENTS: JAMES SMITH BROS., PIPES, LIMITED, 24 HALF MOON LANE, LONDON, S.E.24  
Telephone: Brixton 3000 and 3003



Reinforced Concrete Flats on the Notre Dame Estate, for the Wandsworth Borough Council.  
*Architects : Messrs. James & Bywaters. Consulting Civil Engineers : Messrs. R. T. James & Partners. Contractors : Messrs. Wm. Moss & Sons, Ltd.*

# CONCRETE AGGREGATES supplied by --- **TRUCKEL** ---

Specialist suppliers of the highest quality washed and graded materials for contracts of every size in London and Suburbs and the Home Counties.

Place our name on your list for future inquiries.

WM. TRUCKEL, LTD., BATTERSEA PARK ROAD, LONDON, S.W.8

Telephone: Macaulay 4511 (four lines)




## VIBRATING EQUIPMENT for QUALITY CONCRETE

**PETROL AND ELECTRIC  
INTERNAL VIBRATORS**

**SALE or HIRE**

Manufacturers of vibrating tables, internal vibrators, external vibrators, petrol and electric vibrating tampers, vibrating screens, pan vibrators, electric motors, petrol engines, builders' hoists and winches, and hydraulic bar croppers.



# E. P. ALLAM & CO. LTD.

LONDON: 45 Great Peter Street, S.W.1. Telephone: Abbey 6353 (5 lines)

SCOTLAND: 39 Cavendish St., Glasgow, C.S. Tel.: South 0100. Works: Southend-on-Sea. Tel.: Eastwood 50343

# CONCRETE



Anderson's Concreting Paper, a bituminised waterproof product, is ideal for road or floor concreting. It prevents the water from draining away from the underside of the concrete, and thus allows a uniform set throughout the thickness. Supplied in rolls 112 yards in length and 36 inches wide. Samples and particulars sent on request.

## ANDERSON'S CONCRETING

D. ANDERSON & SON LIMITED, STRETFORD, MANCHESTER  
Roach Road, Old Ford, London, E.3

## PAPER *and* FLEXPAND

EXPANSION JOINTING

# THORNTONS FOR REINFORCED CONCRETE CONSTRUCTION

The long list of contracts of all kinds and sizes carried out by us in reinforced concrete reflects the very wide experience we have had in this class of work. We undertake contracts in any part of the country, and invite Engineers and Architects to include our name on their lists for future enquiries.

*William*

## THORNTON & SONS LTD



38 WELLINGTON ROAD  
LIVERPOOL 8

# The latest developments in prestressed concrete production have been adopted by **ANGLIAN** BUILDING PRODUCTS LTD.

Send your enquiries to:

**ANGLIAN BUILDING PRODUCTS LTD.**  
**LENWADE** Tel.: Gt. Witchingham 91 **NORWICH**



GET that new plant into action quickly—speed up the fixings! Machinery and equipment? Bolt it down same day with Rawlbolts. Screw fixings—wiring, lighting, pipes, switchgear and the rest—fix them fast, firm and permanently with Rawlplugs. Rawlplugs are the world's speediest, vibration-proof fixing devices—in brick, cement, concrete and all types of masonry.

**RAWLPLUG**  
WALL PLUGS


**FIXING DEVICES**

WRITE FOR TECHNICAL LITERATURE

*Use Rawlplug Fixing Devices where "speed is the essence of the contract"*

**THE RAWLPLUG COMPANY LIMITED • CROMWELL RD • LONDON • S.W.7**

# STONE COURT AGGREGATES



*General View of Plant at Rickmansworth.*

## ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS

High-grade concrete aggregates graded to any specification, and the most punctual delivery service in England, can now be given to all Contractors, Builders, and Municipal Authorities carrying out concrete work and road construction in London and Suburbs and the Home Counties.

Washed all-in Ballast 2 in. down.

$\frac{3}{4}$  in. Washed & Crushed or Un-crushed Shingle.

$\frac{1}{2}$  in. Washed & Crushed or Un-crushed Shingle.

Washed Pit Sand.

Soft Sand.

$\frac{3}{16}$  in. Crushed Grit.



**STONE COURT BALLAST CO. LTD.**

PORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.1

Telephone : Abbey 3456.







## — When it comes to stress in tension —

... nothing can better Isteg Steel (and even nature gets mixed up if she tries). Isteg's combination of twist and cold working long ago established its lead in concrete reinforcement—50% extra on tensile stress—30% less weight—15% off the cost—elimination of hooks or overlengths.

No wonder that Designers whose memories go back to the early days of Isteg keep on specifying it over and over again.

# ISTEG

*for Concrete*




*Reinforcement*

# STEEL

**ISTEG STEEL PRODUCTS LTD. (SALES)**

**43, Upper Grosvenor Street, London, W.1. Tel: Grosvenor 1216**

Isteg is manufactured by Guest Keen & Nettlefolds (Cwmbran) Ltd. Cwmbran  
McCall & Co. (Sheffield) Ltd., Templeborough, Sheffield  
The United Steel Companies Ltd., Sheffield and Isteg Steel Products Ltd.



## • GLASCRETE •

Dr. F. F. Curtis, Chief Architect of L.P.T.B. (Western Region), used effectively Glascrete (reinforced concrete and glass) mullion bar windows in his very striking design for Hanger Lane Station, shown above.



**J. A. KING & CO. LTD.**

181 Queen Victoria St. LONDON, E.C.4

—“there's no need to  
paint GLASCRETE”

Telephone : CENTRAL 5866 (6 lines).

**E.L.B.**  
*Wire Ties*

**20 to 30**  
*Ties per minute*

ENGINEERS SPECIFY THEM because reinforcement is securely fixed without fear of displacement by rough usage, tamping, or vibration. No snapped ends are left to cause rust marks.

CONTRACTORS PREFER THEM because they are cheaper and fixed more easily and quickly than any other type. Test them on your next contract at our expense.

... SAVE TIME, LABOUR & MATERIALS

**I. S. & G. MERCHANTS LTD.**

(Formerly EDWARD LE BAS & CO., LTD.)

14 FINSBURY CIRCUS,  
LONDON, E.C.2

\*Phone: London Wall 6805.  
\*Grams: Gramercy, London.

# prestressed and precast concrete for building and civil engineering



A symbol of quality materials, experienced workmanship, expert supervision, and excellent service.

We specialise in the production of prestressed and precast concrete structural members to standard or special designs, including railway sleepers, and shall be pleased to submit quotations for contracts in most parts of the country.

## H. B. CONCRETE CO LTD

Head Office: East Street, Epsom, Surrey.  
Telephone: Epsom 4041/4042.

Branch Works: Vicarage Road, Egham, Surrey.  
Telephone: Egham 3092/3093.

# COLOURS *for* ASPHALT

Introducing a new range specially prepared for  
ASPHALT by the Manufacturers of the well-known

## "SHADEACRETE" COLOURS FOR CEMENT

LET US SEND YOU SAMPLES AND PRICES OF

RED • BLUE • YELLOW • GREEN • BROWN

## W. HAWLEY & SON, LTD.

Colour Works, DUFFIELD, Derby

Phone: Duffield 2294/5

COLOUR MAKERS SINCE 1838

Grams: Hawley, Duffield

## REINFORCED CONCRETE

by

# A. G. MANSELL & CO. LTD

## CIVIL ENGINEERING AND BUILDING CONTRACTORS

BRIDGES - RIVER AND SEA DEFENCE WORKS - WATER TOWERS - BUNKERS  
SILOS - INDUSTRIAL BUILDINGS - ROADS - FOUNDATIONS - AND PILING.

78 BUCKINGHAM GATE, LONDON, S.W.1.

TELEPHONE: WHITEHALL 8735-6-7.



*Is FLOORING your problem?*

*These*

### SEALOCRETE

*Products*

*will help solve it*



BRITISH RAILWAYS SOUTHERN SECTION, OCEAN TERMINAL DOCK  
SOUTHAMPTON

Designed by J. H. Jellett, Esq., Docks Engineer. Chief Assistant Architect:  
C. B. Dromgoole, Esq.

#### SEALOCRETE DOUBLE STRENGTH PREMIX

makes floor toppings dustproof, oilproof, case hardened and permanently waterproof.

#### SEALOCRETE CONCRETE SURFACE DRESSING

applied to newly laid or existing concrete floors renders them dustproof, greaseproof, oilproof and case hardened. Sealocrete Coloured Concrete Surface Dressing in 12 colours for use on floors not subjected to heavy traffic.

#### SEALANTONE LIQUID COLOURS

for incorporating into cement floors, made in 12 standard shades. Over two million yards of coloured concrete flooring have Sealantone Liquid Colours incorporated.

#### SEALOCRETE METALLIC HARDENER

finely graded metallic compound which when incorporated with Granolithic floor toppings gives a very hard surface capable of withstanding extremely heavy usage.

#### SEALOCRETE COLOURED CORK FLOORING

COMPOUND produces a light duty floor which is warm, resilient, colourful and waterproof.

## SEALOCRETE PRODUCTS LIMITED

ATLANTIC WORKS  
HYTHE RD., LONDON, N.W.10

Telephone: LADbroke 0015/6/7.

Telegrams & Cables: Expicture London



## CEMENTATION

WILL SEAL WATER LEAKAGES THROUGH CONCRETE, ROCK OR SUB-SOILS, AND WILL STABILIZE SUB-STRATA TO ARREST SETTLEMENT OF STRUCTURES ON FAULTY FOUNDATIONS. ALSO BY THIS PROCESS DETERIORATION OF CONCRETE OR OF MASONRY WORKS CAN BE REMEDIED.

## BORED PILES

CAST *in situ* PILES CAN BE PUT DOWN TO GREAT DEPTH WITH A MINIMUM OF HEADROOM AND VERY LITTLE VIBRATION, WITH DESIGNED BEARING CAPACITY.  
OUR WIDE EXPERIENCE IS AT YOUR DISPOSAL.

## GUNITE

RECONDITIONING DAMAGED AND DEFECTIVE CONCRETE STRUCTURES.  
ENCASING STRUCTURAL STEELWORK.  
LINING TUNNELS, CULVERTS, RESERVOIRS.  
COVERING THE WEARING SURFACES OF CHUTES AND BUNKERS.

**THE CEMENTATION**  
**CO. LTD.** Telephone Don 54177-4-5 BENTLEY WORKS, DONCASTER.

LONDON OFFICE: 39, VICTORIA STREET, S.W.1  
TELEPHONE: ABBEY 5726-7-8.

# The **PAINT** that **PROTECTS** **ASBESTOS CEMENT** **SURFACES**



EVODE PROTECTIVE (Chlorinated Rubber) PAINTS GIVE THAT EXTRA PROTECTION. EVODE PROTECTIVE PAINTS are highly alkali and acid resisting and are the answer in all cases where a high degree of protection, durability and a pleasing semi-gloss finish are required. Practically fire-proof when dry. No special primer or petrifying liquid required either on asbestos cement or on concrete. Dust dry in half an hour.

For iron, steel, wood and direct painting of asbestos cement sheeting, concrete and concrete floors, brickwork and cement renderings.

EVODE LIMITED, GLOVER ST., STAFFORD • Tel.: 1590/1/2 • Grams: EVODE

## **COPPER STRIPS** for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.



**ALEX J. CHEETHAM LTD.**

MORTON STREET • FAILSWORTH • MANCHESTER

Telephone: FAILSWORTH 1115/6

DS14





AEROFILMS

In times of shortage and difficulty it is essential for buyers to be able to rely on their suppliers. For this reason 'Twistee' was selected by contractors to supply fabric reinforcement to the South Bank site, and 25,000 square yards of Wireweld were used.



LONDON: 43 UPPER GROSVENOR STREET, W.1 • Tel: GROsvenor 1216  
MANCHESTER: 7 OXFORD ROAD, MANCHESTER, 1 • Tel: Ardwick 1691  
BIRMINGHAM: ALMA STREET, SMETHWICK, 40 • Tel: Smethwick 1991  
GLASGOW: 146 ARGYLE STREET, GLASGOW, C.2 • Tel: Central 4551

# GUNITE SPECIALISTS

**W.M. MULCASTER  
& CO. (CONTRACTORS) LTD.**

We invite inquiries for Gunité Linings and Renderings  
for new or old structures of every kind in any part  
of the country.

**HASLINGTON**

Telephone: Crewe 2265-6.

**CREWE**



## THE "JOHN BULL" CONCRETE BREAKER

NEW "B.A.L." TYPE.

**INCREASED :—**

PENETRATION, RELIABILITY, LIFE.

**REDUCED :—**

VIBRATION, NOISE AND WEAR.

THESE ARE THE SALIENT FEATURES  
OF THE NEW CONCRETE BREAKER

★ ★ ★

**REAVELL & CO., LTD.**

**RANELAGH WORKS, IPSWICH.**

TELEGRAMS: "REAVELL, IPSWICH."

TELEPHONE: 2124

# INDUSTRIAL CONSTRUCTION

Factories Offices  
Foundations

KENT & SUSSEX  
CONTRACTORS LTD.

LONDON • SIDCUP • BIRMINGHAM

Government Factory and  
Administrative buildings at  
Chadwell Heath, Essex, by  
Kent & Sussex Contractors

Associated Company - RUSH & TOMPKINS (S.A.) LTD. Durban Natal.



**ALPHA CEMENT LTD**

**PORTLAND HOUSE, TOTHILL STREET**

**LONDON, S.W.1.**

*Telephone - Abbey 3456.*

THE UNITED  
**STEEL**  
COMPANIES LTD



# STEEL JOISTS AND SECTIONS

**APPLEBY-FRODINGHAM STEEL COMPANY**

Branch of The United Steel Companies Limited


**SCUNTHORPE, Lincs.**

Telephone: Scunthorpe 3411 (9 lines)

Telegrams: "Appfrod" Scunthorpe

 A.F.92A

*To the job...on the job...with the job...*



## *Faster with* **REX TRAILER MIXERS**

Rex 5E and 7E Trailer Mixers by reason of highest quality engineering are lighter in weight, making for easier and greater mobility than other similarly rated machines, giving **ECONOMY IN TRANSPORT COSTS**. Furthermore, their fast-only 75 seconds-mixing cycle, together with their intensive end-to-end, top-to-bottom, over-and-under, mixing action, give the most batches per hour of highest quality concrete to any specification — **AT THE LOWEST MIXING COST PER CUBIC YARD OF CONCRETE**. That is why most of the large contractors use REX Concrete Mixers.

**BATCHING, MIXING AND BULK  
CEMENT PLANT • MOTOMIXERS  
CONCRETE MIXERS • CONCRETE  
SPREADERS AND FINISHERS  
ROADFORMS • STEEL SHUTTERING  
CONCRETE PUMPS • DEWATERING  
PLANT • EXCAVATORS • EARTH  
MOVING EQUIPMENT**

BLAW KNOX LTD., 90/94 BROMPTON  
ROAD, LONDON, S.W.3. Tel: KEN 5151.  
I want details of REX Concrete Mixers.

NAME .....

ADDRESS .....





# CONCRETE AND CONSTRUCTIONAL ENGINEERING

Volume XLVI. No. 8.

LONDON, AUGUST, 1951

## EDITORIAL NOTES

### Scarcities.

It is estimated that in Great Britain this year the allocation of steel for reinforcement bars and wires for constructional work is about two-thirds of the requirements, and the precast concrete industry claims that orders are being accepted for only three-quarters of the quantity it needs. This is a striking commentary on the difference between the production of steel and the requirements, for at a time when licences are difficult to obtain for new buildings or even the repair of old ones it would not be justifiable to expect the Ministries and other authorities concerned to grant licences for steel-framed buildings if reinforced concrete structures needing much less steel would be equally satisfactory, or indeed nearly so. This is the state of affairs in the middle of the year 1951. It would be fruitless to try to guess what the position may be in the next few years if the plans for rearmament are put fully into practice and a still greater proportion of the production of steel is used for this purpose.

The construction industry has been accustomed to a scarcity of steel and most other building materials for more than twelve years. Indeed, there is a danger that scarcities have for so long been so large a part of our lives that they may be accepted as normal, and that no real effort will be made to find the true reason and to provide remedies. Reasons are given which appear to be sufficient, and which are generally accepted because to suggest the true reason would be unpopular. It is not, for example, sufficient to say that one of the causes of the shortage of steel is the lack of shipping to bring ore and scrap. At a time when ships are employed bringing coal from America, it is truer to say that the reason is the insufficient production of coal in Great Britain. A few weeks ago it was stated at the annual conference of the biggest trade union in the engineering industry that the rate of production per man had increased recently, and for this reason it was agreed to press for a reduction in the working hours to forty a week. That is, greater output should not be permitted, and as improved methods and machines come into operation the working hours should be reduced so that the previous rate of output is not exceeded. What an encouragement to use brains and spend money on new equipment! A noticeable trend of recent years is the extent to which forms of syndicalism are entering into various industries. In private as well as in nationalised industries there is an increasing tendency for employers and employed to make arrangements satisfactory to themselves but with little or no regard for the

rest of the people who have to pay higher prices or suffer the inconveniences that result from such arrangements.

A few weeks ago the Lord Privy Seal said that the Government depended upon increased output, and pleaded for a 20 per cent. greater effort from workers of all classes. This is the simple remedy for our present scarcities, namely that we all do more work each year. Everyone knows that in nearly every vocation people could do more work each year if they wished to do so or were allowed to do so, but few are willing to give expression to this cure for our scarcities because it would be unpopular to do so. Those who work in offices for as few as thirty-five hours a week and have up to a month's holiday a year would be loath to have this changed. Manual workers—or at least their leaders—look upon the five-days' week and a fortnight's holiday each year as a great step forward in what they call the "emancipation of the working classes", and an idle Saturday has become something sacrosanct which must not be interfered with however great the scarcities, hardships, inconvenience, and increased costs to them and the rest of the people—or, indeed, however much many of those who work five days a week would prefer to work also on Saturday mornings. Many of our scarcities are due to the fallacious claim that as much work could be done in five days as in five-and-a-half, ignoring the fact that in some of the most important industries the speed of the machine and the period it is working alone control the volume of production.

More leisure for all is very desirable if we can afford it, but it seems certain that in the past few years man has come to expect too many commodities and comforts for the amount of work he is prepared to do, with the result that the goods he produces are not sufficient for his needs, and the consequent higher prices and higher wages which buy ever fewer goods, because goods are produced by work and not by money. During the war and for a year or two afterwards we were told that the problem would be solved by scientists and technologists who would invent machines and processes that would vastly increase production without increased human effort. This has not happened. We were then told that management was at fault, but the visits to the United States of deputations from all sides of British industry have found that the lower production in Great Britain can be more often attributed to the desire to prevent unemployment even to the extent of refusing to use, or not fully using, labour-saving machinery, a disinclination to work more than one shift a day, and wage rates which give skilled men little more than labourers. The desire for more leisure is understandable, but insistence on being idle when we could be making the things we ourselves want is not. It is generally agreed that there would have been much unemployment in this country in the past few years if it were not for such fortuitous happenings as the gifts we have had from abroad, the keeping of nearly a million men in the armed forces, the swollen Civil Service, and now the work of rearmament. Such aids to employment will not for ever replace one another. We are very ready to listen to writers and talkers who claim that our economic problems can be solved by paper transactions such as altering the value of money, trading agreements, government control of our personal affairs and of industry, and other devices which do not suggest that people should do more work. Should we not realise that more work done now is the only remedy for our scarcities and the best insurance against unemployment and distress?

## Wharf and Tunnels at Electricity Works.

THE new electricity power station for the British Electricity Authority at Bank-side, London, will have oil-fired boilers. The oil will be discharged from tankers at a new wharf in the river Thames and will be pumped through pipes in a tunnel under the river bank and power-house to storage tanks at the rear of the power-house. Cooling water taken from the

The deck, which is 8 ft. 6 in. above high-water and is generally a 12-in. reinforced concrete slab, carries buildings to accommodate the pumps and electrical equipment. The consulting civil engineers to the British Electricity Authority are Messrs. Mott, Hay and Anderson, and the contractors are Sir Robert McAlpine & Sons, Ltd.




Fig. 1.—Excavation for Upstream Part of Wharf, showing Steel Struts in Cofferdam.

river at the wharf will flow through the intake tunnel to a suction chamber, and will be returned through the outfall tunnel which passes under the river and will discharge the water near the opposite bank. There is also an access tunnel from the wharf to the power-house.

The wharf (*Figs. 1 to 5 and 8*) is 290 ft. long and 38 ft. wide, and is designed to accommodate tankers carrying about 500 tons as well as smaller boats. The structure is in two parts; the upstream part is of cellular and mass construction and contains the water-intake works and the entrance to the access tunnel as in Section 2—2, and the downstream part is of open construction as in Section 1—1 (*Fig. 3*).

August, 1951.

### Intake Works.

The general level (— 24 ft. O.D.) of the foundation of the upstream part is 35 ft. 6 in. below high water and is generally a 7-ft. concrete slab laid on the clay. The shafts to the entrances of the access and intake tunnels extend about 28 ft. below the general foundation level. The reinforced concrete columns between the intake screens, the intake shaft, and well for the lift and stairs to the access tunnel are shown in *Figs. 1 and 8*.

This part of the wharf is being constructed in a steel sheet-pile cofferdam 96 ft. long and about 37 ft. wide and, when excavated, the depth was about 43 ft. The walings and struts were of welded




Fig. 2.—Wharf during Construction.




Fig. 3.—Cross Sections of Wharf.

steel and were successively dismantled as concreting proceeded (Fig. 1). After the shafts to the tunnels had been sunk from the bottom of the excavation and lined with cast-iron segments, the work proceeded in the stages shown in Fig. 9, namely: (1) Concrete was placed up to -21.5 ft. and, when it had hardened, the lowest setting of walings and struts was removed. (2) The remainder of the concrete in the foundation slab up to -17 ft. and in the walls for a height of 2 ft. up to -15 ft. was placed. The part of the wall at the rear of the wharf is reinforced as a horizontal beam  $R_1$  and acted temporarily as a waling; when the concrete had hardened, shortened struts  $S_1$  were placed between the beam and vertical timbers  $V$  bearing against the

steel walings at the front of the wharf. It was then possible to remove the second setting of struts at -14 ft., and the steel waling at this level at the rear. (3) Procedure similar to (2) enabled concrete to be placed in the walls and screen-columns  $C$  up to -8.5 ft., a horizontal reinforced concrete beam  $R_2$  and a shortened strut  $S_2$  being provided; the steel struts and rear waling at -7.5 ft. could then be removed. (4) Concrete was placed up to +1.0 ft., including a reinforced concrete slab at -1.0 ft. and a beam  $R_3$ . Except for the front walings, the steel walings and struts at +2.0 ft. were removed. (5) The concrete in the walls and piers up to +13.0 ft. was placed. The walings and struts at +14.0 ft. were then replaced by timber strutting and the



shuttering for the deck was erected. The cofferdam will be removed when the intake works are sufficiently advanced to permit this shaft and the tunnel to be flooded.

**Open Part of Wharf.**

The deck of the downstream part of the wharf is supported on eight pairs of piers. For each pier, a cylinder of steel sheet-piles of 8 ft. diameter was driven to the clay at about - 23.0 ft., the tops of the piles being at - 3.0 ft. The ground within the cylinders was excavated by grab, and four 12-in. square precast reinforced concrete piles were driven through the cylinders into the ground below each pier down to at least - 35.0 ft. The piles are 45 ft. long and are at an inclination of 1 in 40. They were driven by a 2½-ton steam-hammer dropping 4 ft. 6 in. to a set of ¼ in. per blow. The cylinders were filled with concrete up to - 11.0 ft., the concrete being placed under water through a tremie. From - 11.0 ft. upwards the piers are constructed with spun reinforced concrete pipes (*Fig. 4*) in 6-ft. rings of 6 ft. 8 in. outside diameter, filled with concrete, and stabilised above low-water level by horizontal and inclined precast reinforced concrete braces (*Fig. 3*). At the junction of a pier and brace, the wall of the top pipe was broken into, and



the wharf will comprise 12-in. square main timber piles at 6-ft. centres connected to the jetty only at the deck. Intermediate support will be provided by two 12-in. by 9-in. timber walings at + 1.5 ft. and + 11.0 ft. The walings will bear on an inner row of 12-in. square timber piles driven at 12-ft. centres midway between

each pile and the concrete. The pile will bear against, but will not be secured to, the concrete brace at - 1.0 ft., to which will be attached a 3½-in. rubber pad protected by a ½-in. steel plate. The piles will be protected from direct blows from vessels by a horizontal 18-in. square floating timber boom, which will slide up and



**Fig. 6.—Brick Facing to Concrete Lining.**



**Fig. 7.—Precasting Lining for Tunnel.**

pairs of main fender piles, and secured to the deck of the wharf and to the longitudinal reinforced concrete brace at - 1.0 ft.

The fendering on the front of the wharf, where the largest vessels will berth, will comprise 14-in. square vertical timber piles secured directly to the wharf only at the deck (*Figs. 3 and 5*), where a rubber pad 4 in. thick will be placed between

down chains as the water rises and falls. The boom will be in lengths of about 24 ft., and two chains will be provided for each length. The chains will be suspended from the deck and be anchored in pairs to a block of cast iron 2 ft. wide, 2 ft. 2 in. deep, and generally 10 ft. long, and about 8 tons in weight.

At the rounded ends of the jetty, the fendering will comprise 12-in. by 8-in.




Fig. 8.—Elevation







Fig. 9.—Stages in C



WHARF & INTAKE BLOCK

and Plan of Wharf.



Section of Intake Works.

vertical steel beams, most of which will be driven as piles at about 3-ft. 3-in. centres. The beams will not be fixed directly to the jetty, but will have on the back flange 2-ft. square plates which will bear against continuous hard-rubber bands at the levels of the deck and of the brace at - 1.0 ft. The upper band will be 12 in. by 9 in., and the lower 12 in. by 6 in. Forward movement of the beams will be prevented by a plate attached to the concrete and overlapping the edges of the plates on the beams.

### **The Tunnels.**

The intake and outfall tunnels, which are in clay, are 10 ft. diameter and are constructed of cast iron segments lined with concrete. The intake tunnel was driven in free air, but the outfall tunnel,

which passes under the river, was driven in compressed air.

The access tunnel serves as a footway between the power-house and the wharf and will accommodate the oil pipes. It is in clay and was driven in free air. It is 10 ft. diameter and lined with precast concrete segments and engineering bricks (Fig. 6). The segments were cast on the site (Fig. 7) on curved centering, the rebates for the interlocking joints being formed by shaped steel plates. The segments, of which there are twelve in each ring, are placed in position by hand, and grout is forced under pressure behind the lining through holes cast in the segments. The segments are of different lengths, and weigh from 200 lb. to 300 lb. each. They are 12 in. wide, and  $5\frac{1}{2}$  in. thick. Each ring of segments is reinforced by one  $\frac{7}{8}$ -in. diameter bar, bent to a circle and grouted in the groove between the rings.

### **A Concrete Plant of High Output.**

THE rate of concreting at the Bull Shoals dam, Arkansas, the construction of which is described in a recent number of "Concrete," is nearly 7,000 cu. yd. in 24 hours. The plant is capable of producing 8000 cu. yd. in 24 hours and comprises principally four 4-cu.-yd. mixers. The aggregates are brought seven miles by a belt-conveyor to crushing and screening plants at the site, and are transported to bins by conveyors in tunnels under the stockpiles. Two cylindrical steel bins, each of 138 tons capacity, are provided for each size of aggregate, thereby enabling the material in one bin to cool while that in the other is being used. Cooling is accomplished by continuous circulation through the aggregate of water at 35 deg. F. The sand is not cooled. The temperature of the concrete when placed is from 53 deg. to 63 deg. F. in

summer and 42 deg. to 52 deg. F. in winter.

Above the mixers are four bins for coarse aggregates, one for sand and two for cement. The materials are automatically weigh-batched. The concrete is discharged into a hopper from which 4-cu.-yd. buckets are filled. A rail-wagon carrying four buckets, with space for another, is drawn to the site. A hammer-head crane (one of several travelling on a gantry parallel to the dam) places empty buckets in the unoccupied spaces and lifts a full bucket. When the fourth full bucket is taken, the wagon is returned to the mixing plant and this bucket, when empty, is placed on the next wagon. In this way more than 400 wagons each conveying 16 cu. yd. are unloaded daily when concrete is placed at the maximum rate.

### **A Large Reinforced Concrete Cooling Tower.**

A REINFORCED concrete hyperbolic cooling tower recently completed at Stanlow refinery, Ellesmere Port, is thought to be the largest in the world. The tower, which is 341 ft. 6 in. high, will have a cooling

capacity of 5,000,000 gallons per hour. The diameter at the base is 222 ft., at the neck 168 ft., and at the top 177 ft. The tower weighs about 20,000 tons and contains about 500 tons of reinforcement.

## Bending Moments due to Temperature Changes in Continuous Reinforced Concrete Structures.

By ALBIN CHRONOWICZ.

THE distortion of a structure due to temperature changes may be due to different temperatures of two opposite faces of a member causing warping, or to the expansion or contraction of a member as a whole.

### Different Temperatures of Opposite Faces of a Member.

In this case, referring to Fig. 1, if  $T_2 - T_1 = \Delta T$ , the extension of the hot face and contraction of the cold face is  $\frac{\Delta T}{2} \epsilon \cdot ds$ , which must equal  $\frac{d_0}{2} d\theta$  if  $\epsilon$  is the coefficient of thermal expansion. Hence  $\frac{d\theta}{ds} = \frac{\Delta T \cdot \epsilon}{d_0}$ . Since  $\frac{ds}{R} = d\theta$ ,  $\frac{d\theta}{ds} = \frac{1}{R} = \frac{M}{EI}$ ; therefore the bending moment  $M$  produced by the difference of temperature is  $\frac{\Delta T \cdot EI \epsilon}{d_0}$ . Restraining bending moments of the magnitude of  $M$  are required to produce a curvature to counteract the curvature due to the difference of temperature, and have the effect of end-fixity producing tension at the cold face.

It can generally be assumed that a reinforced concrete member cracks if it is subjected to a temperature exceeding 60 deg. F. Therefore the evaluation of the restraining bending moments should be based on the cracked section, neglecting in the calculation of the moment of inertia  $I$  that part of the concrete which is in tension. Therefore, referring to Fig. 2a,  $I = \frac{b(n_1 d)^3}{3} + mA_s(d - n_1 d)^2$ .




Fig. 1.




Fig. 2.




Fig. 3.




Fig. 4.

The curves in Figs. 3 and 4 give values of  $I$  in terms of  $bd^3$  for "cracked" sections of rectangular beams (with and without compressive reinforcement) and tee-beams, assuming  $m = 15$ . For a wall or slab of a total thickness  $d_0$ , and  $b$  of 12 in., the average value of  $I$  is about  $d_0^3$ .

Assuming  $\epsilon$  to be about 0.00006 per degree Fahrenheit and the elastic modulus  $E$  of concrete to be about 2,000,000 lb. per square inch, the product  $\epsilon E$  is about 12. Assuming also a uniform flow of heat through the wall, if  $T_i$  and  $T_o$  are the air temperatures (Fig. 2b),  $\phi$  the coefficient of heat transmission of the



wall, and  $\lambda$  the coefficient of conductivity of the material of the wall,  $d_0$  the thickness (feet) of the wall, and  $\alpha_i$  and  $\alpha_o$  the coefficients of radiation at the inside and outside faces respectively, the following apply to 1 sq. ft. of the face of the wall:

Total amount of heat lost through wall:  $Q_1 = \phi(T_i - T_o)$ .

Amount of heat entering the hotter face:  $Q_2 = \alpha_i(T_i - T_1)$

" " " passing through the wall:  $Q_3 = \frac{\lambda}{d_o}(T_1 - T_2)$

" " " leaving the cooler face:  $Q_4 = \alpha_o(T_2 - T_o)$

For a constant flow of heat,  $Q_1 = Q_2 = Q_3 = Q_4$ . Since  $T_1 - T_2 = \Delta T$ , combining the foregoing expressions gives  $\Delta T = \frac{T_i - T_o}{\frac{1}{\phi} \frac{d_o}{\lambda}}$ .

If the wall comprises layers of different materials of thickness  $d_1, d_2, d_3, \dots$

$$d_n \text{ (ft.)}, \frac{1}{\phi} = \frac{1}{\alpha_i} + \frac{d_1}{\lambda_1} + \frac{d_2}{\lambda_2} + \dots + \frac{d_n}{\lambda_n} + \frac{1}{\alpha_o}.$$

Common values of  $\lambda$ , when the units are feet and degrees Fahrenheit, are: For concrete, 1; gypsum, 0.3; brick, 0.5; slag-wool, 0.1; cork, 0.06. The coefficient of radiation ( $\alpha_i = \alpha_o$ ) for concrete is about 2.

EXAMPLE NO. 1.—Determine the restraint bending moments due to the difference of temperature on two sides of a reinforced concrete slab ( $\lambda = 1$ ;  $\alpha_i = \alpha_o = 2$ ;  $E = 12$ ), for which  $d_0 = 0.5$  ft.,  $T_i = 120$  deg., and  $T_o = 30$  deg. F. By substitution,  $\frac{1}{\phi} = \frac{1}{2} + \frac{0.5}{1} + \frac{1}{2} = 1.5$ , and  $\Delta T = \frac{120 - 30}{1.5} = 30$  deg. F. Since  $I = d_0^3$  (approximately)  $= 6^3 = 216$  in.<sup>4</sup>, the fixed-end bending moment due to the difference of temperature is given by  $M = \frac{30 \times 12 \times 216}{6} = 13,000$  in.-lb.

Adjustments can be made by the usual moment-distribution method.

### Members Subjected to Uniform Change of Temperature.

Assume that the members of the frame in Fig. 5 are subjected to expansion due to a rise of temperature. By the usual process of strain-energy analysis,

$$M_{AB}^x = Hx; \quad \frac{\delta M}{\delta H} = x; \quad \frac{\delta U}{\delta H} = \int_0^h \frac{M \frac{\delta M}{\delta H} dx}{EI}$$

$$M_{BC}^x = Hh; \quad \frac{\delta M}{\delta H} = h; \quad \frac{\delta U}{\delta H} = \int_0^l \frac{M \frac{\delta M}{\delta H} dx}{EI}$$

Hence

$$\epsilon T l = \frac{\delta U}{\delta H} = \frac{2H}{EI} \int_0^h x^2 dx + \frac{Hh^2}{EI} \int_0^l dx,$$

$$\frac{2Hh^3}{3} + Hh^2 l = \epsilon T l EI,$$

from which

$$H = \frac{3\epsilon T l EI}{h^2(3l + 2h)}, \text{ and } M_{BA} = \frac{3\epsilon T l EI}{h(3l + 2h_3)}.$$

By moment distribution (Fig. 5), the fixed-end bending moments are  $\frac{3EI}{h^2} \epsilon \frac{l}{2} T$ . Because of symmetry the distribution factors are:


$$\gamma_{BA} = \frac{\frac{3}{4h}}{\frac{3}{4h} + \frac{1}{2l}} = \frac{3l}{3l + 2h}, \text{ and } \gamma_{BC} = 1 - \gamma_{BA} = \frac{2h}{3l + 2h}.$$

The moment-distribution operations are shown in Fig. 5.

It follows that thermal extension of the members of a frame can be regarded as displacement of the respective joints and the resulting fixed-end bending moments are distributed in the usual way.

EXAMPLE NO. 2.—The reinforced concrete duct (Fig. 6) for the passage of hot gases will be analysed. The frame constants are  $\frac{I_{BC}}{I_{AB}} = \frac{0.5^3}{0.33^3} = 3.4$ . Since relative values of  $I$  only are needed,  $I_{AB} = 1$  and  $I_{BC} = 3.4$ . Therefore the stiffness factors are:  $K_{AB} = \frac{1}{3} = 0.125$ , say, 1 unit;  $K_{BC} = \frac{3.4}{14} = 0.243$  unit;  $\frac{K_{BC}}{2} = 0.12 = 1$  unit; and, because of the symmetry of the frame,  $\gamma_{BC} = 0.5$ .

(i) Distortion due to differences of temperature.—For AB (Fig. 6c),  $T_i - T_o = 240$  deg. F. Therefore  $\frac{I}{\phi} = \frac{I}{2} + \frac{0.33}{1} + \frac{I}{2} = 1.33$ , and  $\Delta T_{AB}$  is



BA	BC	
$\frac{3l}{3l+2h}$	$\frac{2h}{3l+2h}$	Moment-distribution factors.
$\frac{3EI}{h^2} \epsilon \frac{l}{2} T$		Fixed-end moments.
$-\frac{3EI}{h^2} \epsilon \frac{l}{2} T \frac{3l}{3l+2h}$	$-\frac{3EI}{h^2} \epsilon \frac{l}{2} T \frac{2h}{3l+2h}$	Distribution.
$\frac{3\epsilon T l^2 EI}{h(3l+2h)}$	$-\frac{3\epsilon T l^2 EI}{h(3l+2h)}$	Final bending moments.

Fig. 5.




Fig. 6.

$\frac{240}{1.33} \times 0.33 = 60$  deg. F. Also  $I = 4^3 = 64$  in.<sup>4</sup> The fixed-end bending moment due to difference of temperature is therefore given by

$$M = \frac{60 \times 12 \times 64}{4} = 11,500 \text{ in.-lb. approximately.}$$

For BC (Fig. 6b),  $\frac{I}{\phi} = \frac{1}{2} + \frac{0.5}{1} + \frac{1}{2} = 1.5$ ;  $I = 6^3 = 216$  in.<sup>4</sup>; and

$$\Delta T = \frac{240}{1.5} \times 0.5 = 80 \text{ deg. F. Therefore } M = \frac{80 \times 12 \times 216}{6} = 34,600 \text{ in.-lb.}$$

The moment-distribution operations and the resulting bending-moment diagram are shown in Fig. 6d and e.

(ii) Distortion due to expansion of the members.—The average rise of temperature  $T$  is  $\frac{1}{2}(T_1 - T_0) = 120$  deg. F. Therefore

$$2\delta = \epsilon l T = 0.000006 \times 14 \times 120 \times 12 = 0.121 \text{ in.,}$$

and the fixed-end bending moment (Fig. 6f) is given by

$$M_{AB} = \frac{6EI\delta}{h^2} = \frac{6 \times 2,000,000 \times 64 \times 0.06}{96^2} = 5000 \text{ in.-lb.}$$

The moment-distribution operations are given in Fig. 6g and the bending-moment diagram in Fig. 6h. Combining the effects of (i) and (ii), the final bending moments, as shown in Fig. 6j, are

$$M_{BA} = +23,050 + 2500 = +25,550 \text{ in.-lb.},$$

and

$$M_{AB} = -5725 + 3750 = -1975 \text{ in.-lb.}$$

EXAMPLE NO. 3.—The reinforced concrete testing-tunnel shown in Fig. 7 will be analysed.




Fig. 7.

Frame constants:

$$I_{AC} = 6^3 = 216 \text{ in.}^4; K_{AC} = \frac{216}{21} = 10.3 = 1.$$

$$I_{AB} = I_{CD} = 216 \text{ in.}^4; K_{CD} = \frac{216}{9} = 24 = 2.3 = K_{AB}.$$

$$I_{DB} = 9^3 = 730 \text{ in.}^4; K_{DB} = \frac{730}{21} = 34.8 = 3.4.$$

$$I_{BB'} = I_{DD'} = 730 \text{ in.}^4; \frac{K_{DD'}}{2} = 0.5 \times \frac{130}{13} = 28.1 = 2.7 = \frac{K_{BB'}}{2}.$$

Moment-distribution factors:

$$\gamma_{CA} = \frac{1}{3.3} = 0.3; \gamma_{CD} = 0.7; \gamma_{DC} = \frac{2.3}{8.4} = 0.27; \gamma_{DB} = \frac{3.4}{8.4} = 0.4; \gamma_{DD'} = 0.33.$$

(i) Fixed-end bending moments due to distortion due to differences of temperature.

For members CA and CD,  $T_i - T_o = 120$  deg. F.,  $I = 216 \text{ in.}^4$

$\frac{1}{\phi} = \frac{1}{2} + \frac{0.5}{1} + \frac{1}{2} = 1.5$ , and  $\Delta T = \frac{120}{1.5} \times 0.5 = 40$  deg. F. The fixed-end bending moment is  $\frac{40 \times 12 \times 216}{6} = 17,300 \text{ in.-lb.}$  approximately.

For member BD,  $T_i - T_o = 150$  deg. F.;  $I = 730 \text{ in.}^4$ . The value of  $\lambda$  for steel is large, and  $\frac{d}{\lambda}$  for steel sheets is assumed to be negligible;  $\alpha$  for the face of steel is assumed to be 1.5. Hence,  $\frac{1}{\phi} = \frac{1}{2} + \frac{0.75}{1} + \frac{0.25}{0.1} + \frac{1}{1.5} = 4.4$  approximately, and  $\Delta T = \frac{150}{4.4} \times 0.75 = 25.5$  deg. F. The fixed-end bending moment is  $\frac{25.5 \times 12 \times 730}{9} = 25,000 \text{ in.-lb.}$  approximately.

For member DD',  $T_i - T_o = 270$  deg. F.,  $I = 730 \text{ in.}^4$ ,  $\frac{1}{\phi} = 4.4$ ,

$\Delta T = \frac{270}{4.4} \times 0.75 = 46$  deg. F., and the fixed-end bending moment is

$$\frac{46 \times 12 \times 730}{9} = 45,000 \text{ in.-lb.}$$

(ii) Fixed-end bending moment due to distortion due to expansion of the members.

The members of the frame have freedom of horizontal movement, but the vertical expansion of members BD and B'D' is restricted because of the smaller rise of temperature of members AB and A'B', a condition which produces bending of members CD and C'D'. From Fig. 7c,  $\delta_{CD} = \Delta_{BD} - \Delta_{AC}$ . For  $\Delta_{AC}$ ,  $T = \frac{150 - 30}{2} = 60$  deg. F. For  $\Delta_{BD}$ ,  $T = \frac{300 + 150}{2} - 30 = 195$  deg. F.

Hence, for  $\delta_{CD}$ ,  $T = 195 - 60 = 135$  deg. F., and

$$\delta_{CD} = 135 \times 0.000006 \times 252 = \text{about } 0.2 \text{ in.}$$

The fixed-end bending moment at C in CD is

$$\frac{6 \times 216 \times 0.2 \times 2,000,000}{108^2} = 44,500 \text{ in.-lb.}$$

The moment-distribution operations are given in *Fig. 7d* and the diagram of the final bending moments in *Fig. 7e*.


EXAMPLE NO. 4.—The elevated smoke-precipitator structure in *Figs. 8 and 9* will be analysed.

Frame constants (*Fig. 9a*). Assume that for members AB, BB', and BC,  $p = 1.75$  per cent. and  $a = 2$  in. Then, from the curves in *Fig. 3*,  $I = 1.8 \times \frac{b \times 14^2}{12}$ . Therefore  $I_{AB} = 7350 \text{ in.}^4$ ,  $I_{BB'} = 6150 \text{ in.}^4$ , and  $I_{BC} = 5510$

in.<sup>4</sup> Therefore  $\frac{1}{2}K_{AB} = 0.75 \times \frac{7350}{22.75} = 243 =$ , say, 1.59 units;

$$\frac{1}{2}K_{BB'} = 0.5 \times \frac{6150}{20} = 153 = 1 \text{ unit}; \text{ and } K_{BC} = \frac{5510}{16.75} = 329 = 2.15 \text{ units.}$$

In these members, the flange is on the tension side or coincides with the neutral



**Fig. 8.**






Fig. 9.

axis; therefore the flange is neglected in the calculation of the moment of inertia and stiffness of the member. In member CC', the flange is on the compression side and must be included in the evaluation of  $I$  and  $K$ . Assuming  $p = 3$  per cent. and  $a = 2$  in., for  $\alpha = \frac{6}{0.75} = 8$  and  $\beta = \frac{6}{22} = 0.27$ , from the curves in Fig. 4,

$I_{CC'} = 3 \cdot I \times \frac{9 \times 22^3}{12} = 24,800 \text{ in.}^4$ , and  $\frac{1}{2} K_{CC'} = 0.5 \times \frac{24,800}{20} = 620 = 4.05 \text{ units}$ .

The amount of reinforcement assumed is based on a preliminary design for static loads only.

Moment distribution factors:

At joint B,  $\gamma_{BA} = \frac{1.59}{4.74} = 0.33$ ,  $\gamma_{BB'} = \frac{1}{4.74} = 0.21$ , and  $\gamma_{BC} = 1 - (0.33 + 0.21) = 0.46$ .

At joint C,  $\gamma_{CC'} = \frac{4.05}{6.20} = 0.65$ , and  $\gamma_{CB} = 1 - 0.65 = 0.35$ .

(i) Fixed-end bending moments due to differences of temperature.

It is necessary first to consider the heat transference through a tee-member, such as AB (Fig. 9b). The total loss of heat  $Q_1$  across a member of superficial area  $A$  is  $\phi A (T_i - T_o)$ . The heat  $Q_2$  entering the member is  $\alpha_i n_i A (T_i - T_1)$  if  $n_i$

is the ratio of the area of the surface of the rib corresponding to unit area ( $b \times 1$ ) of the opposite face. Therefore  $n_i = \frac{2d_r + b}{b}$ . The heat  $Q_4$  leaving the outside face is  $\alpha_o A(T_3 - T_o)$ , and the heat  $Q_3$  passing through the member is  $\frac{\lambda}{d_T} A(T_1 - T_2)$ , where it is assumed that  $d_T$  is the "gradient depth" and the temperature of the cracked rib is  $T_i$  approximately. As before,  $Q_1 = Q_2 = Q_3 = Q_4$  and, by combining the expressions for these quantities,

$$\Delta T = T_1 - T_2 = \frac{T_i - T_o}{\frac{1}{\phi}} \cdot \frac{d_T}{\lambda}, \text{ and } \frac{1}{\phi} = \frac{1}{n_i \alpha_i} + \frac{d_T}{\lambda} + \frac{1}{\alpha_o}.$$

In the present example, for member AB,  $n_i = 1 + \frac{28}{12} = 3.33$ ;  $d_T = 0.83$  ft. ;

$T_i - T_o = 220$  deg. F. ;  $\frac{1}{\phi} = \frac{1}{3.33 \times 2} + \frac{0.83}{1} + \frac{1}{2} = \text{about } 1.48$ ; and

$\Delta T = \frac{220 \times 0.83}{1.48} = 123$  deg. F. The fixed-end bending moment  $M_{BA}$  is  $\frac{123 \times 12 \times 7350}{16} = 680,000$  in.-lb.

For member BB',  $T_i - T_o = 100$  deg. F. ;  $d_T = 0.92$  ft. ;  $n_i = 1 + \frac{2.4}{10} = 3.4$  ;

$\frac{1}{\phi} = \frac{1}{3.4 \times 2} + \frac{0.92}{1} + \frac{1}{2} = 1.57$ ; and  $\Delta T = \frac{100 \times 0.92}{1.57} = 58.5$  deg. F. The

fixed-end bending moment  $M_{BB'}$  is  $\frac{58.5 \times 12 \times 6150}{16} = 270,000$  in.-lb.

For member BC (Fig. 9c),  $T_i - T_o = 120$  deg. F. Because of the different shape of the cross section,

$$b = \frac{b_i + b_o}{2}; \quad n_i = \frac{2d_{ri} + b_i}{b}; \quad n_o = \frac{2d_{ro} + b_o}{b}; \quad \frac{1}{\phi} = \frac{1}{n_i \alpha_i} + \frac{d_T}{\lambda} + \frac{1}{n_o \alpha_o}.$$

Substituting the numerical values  $b_i = b_o = b = 9$  in.,  $d_{ri} = d_{ro} = 7$  in.,

$n_i = n_o = 1 + \frac{14}{9} = 2.56$ , and  $d_T = 1.3$  ft., in these expressions,  $\frac{1}{\phi} = 1.69$  and

$\Delta T = \frac{120 \times 1.3}{1.69} = 93$  deg. F. The fixed-end bending moment  $M_{BC}$  is  $\frac{93 \times 12 \times 5510}{16} = 385,000$  in.-lb.

For member CC',  $T_i - T_o = 120$  deg. F. ;  $d_T = d = 2$  ft. ;

$n_o = 1 + \frac{2 \times 1.5}{0.75} = 5$ ;  $\frac{1}{\phi} = \frac{1}{2} + \frac{2}{1} + \frac{1}{2 \times 5} = 2.6$ ; and  $\Delta T = \frac{120 \times 2}{2.6} = 92$  deg. F.

The fixed-end bending moment  $M_{CC'}$  is  $\frac{92 \times 12 \times 24,800}{22} = 1,245,000$  in.-lb.

The directions of action of these bending moments are shown in *Fig. 9d*.

(ii) Fixed-end moments due to expansion of the members.

In *Fig. 9e*,  $\delta_{AB} = \frac{1}{2}\Delta_{BB'}$ , where  $\delta_{AB}$  is the displacement of the joints of member AB and  $\delta_{BB'}$  is the extension of member BB' due to the rise of temperature  $T$  of  $\frac{250 + 150}{2} - 30 = 170$  deg. F. Hence  $\delta_{AB} = \frac{1}{2}\epsilon T l_{BB'}$ , and the fixed-end bending moment is given by

$$M_{BA} = \frac{3EI_{AB}\delta_{AB}}{l_{AB}^2} = \frac{3I_{AB}Tl_{BB'}\epsilon E}{2l_{AB}^3} = \frac{3 \times 7350 \times 170 \times 240 \times 12}{2 \times 273^3} = 72,000 \text{ in.-lb.}$$

Also,  $\delta_{BC} = \frac{1}{2}(\Delta_{BB'} - \Delta_{CC'})$ . For member CC',  $T$  is  $\frac{150 - 30}{2} = 60$  deg. F. Also  $\Delta_{CC'} = \epsilon \times 60 \times 240$ , and  $\Delta_{BB'} = \epsilon \times 170 \times 240$ . Hence  $\delta_{BC} = 13,200\epsilon$ . The fixed-end bending moments are given by

$$M_{BC} = M_{CB} = \frac{6 \times 5510 \times 13,200 \times \epsilon E}{201^2} = 130,000 \text{ in.-lb., if } \epsilon E = 12.$$

The moment-distribution operations are shown in *Fig. 9* and the diagram of the final bending moments in *Fig. 9g*.

These calculations are based on assumed amounts of reinforcement. When the final sections have been designed, the actual values of  $p$  and  $I$  should be compared with the assumed values, and if there are large discrepancies the calculations should be repeated.

### Designs of Dams and Tunnels.

In a paper by Mr. C. M. Roberts, M.Inst.C.E., on "Fundamental Economics in Hydro-electric Design," published in the *Journal of the Institution of Civil Engineers* for April, 1951, comparative costs of dams and tunnels are given.

The first example is a dam with a maximum height of 134 ft. and a length along the crest 950 ft.; sound rock occurs near the surface, and a mound of rock at about the middle of the length of the dam makes a double-arch dam with a central abutment practicable. A round-head buttress dam is the most economical. The cost of a solid gravity dam would be 77 per cent. greater, and of a double-arch dam 94 per cent. dearer. It is stated that the cost of the better concrete and more complex shuttering in the buttress dam would be more than offset by the smaller volume of concrete required compared with the gravity dam.

The dam in the second example is

240 ft. high and 930 ft. long. A round-head buttress dam would again be the cheapest, the cost of a solid gravity dam being 88 per cent. greater. The cost of a single-arch dam would be more than twice that of a buttress dam because the valley is not sufficiently narrow for an arch dam of such height to be economical.

The costs of lined and unlined rock tunnels are also considered. It is shown that, in countries where labour is dear and cement comparatively cheap, a tunnel of 11 ft. equivalent diameter lined with concrete would be the most economical. The cost of an unlined tunnel of 16 ft. 6 in. equivalent diameter, with the same hydraulic properties as the lined tunnel, would be 6 per cent. greater, and that of an unlined tunnel, 15 ft. 9 in. equivalent diameter with a concrete invert and the same hydraulic properties, 13 per cent. greater.




Fig. 2.—Residential Flats in South London.

(See facing page.)

## Residential Flats in South London.

SOME features of the reinforced concrete construction of six blocks of residential flats (*Fig. 1*) being built for the Wandsworth Borough Council on the Notre Dame estate, Clapham, are described in the following. The lengths of the buildings, which are arranged as shown in *Fig. 2*, vary from about 130 ft. to 170 ft. There are no expansion joints. The story height is 9 ft. 3 in. Five buildings are of nine stories and are about 90 ft. high, and the other is of seven stories.

5½ cu. ft. of uncombined fine and coarse aggregate (1:1½:3 by volume). In the party walls and columns below the first floor the proportions are 1:1:2. The working compressive stress in the 1:1½:3 concrete is 850 lb. per square inch, and the maximum tensile stress in the mild steel reinforcement is 18,000 lb. per square inch. The average crushing strength of cubes of 1:1½:3 concrete is 4000 lb. per square inch at 28 days.

The concrete is mixed in a central



**Fig. 1.**

The width of each building is about 26 ft. excluding the balconies.

The floors, balconies, party walls, stairs, and roofs are of reinforced concrete, and the outer walls of brick. The main load-carrying members are the party walls, which are at 15 ft. centres in four of the structures and at 18 ft. 9 in. centres in the other two, and rectangular columns midway between the party walls along one face of each building. The 6-in. solid floor slabs, a typical cross-section of which is shown in *Fig. 2*, span between three lines of longitudinal reinforced concrete beams which are supported on the party walls and columns. The structures are designed for the superimposed loads specified in the by-laws of the London County Council. The foundation is generally clay on which the bearing pressure does not exceed 3 tons per square foot.

The mixture of the concrete is generally 1 cwt. of ordinary Portland cement to

mixing plant which comprises steel aggregate bins, which are filled by a crane-grab, a swivel-type weigh-batcher for measuring the aggregates, and a ½-cu. yd. electrically-driven non-tilting drum mixer. The concrete is discharged into cylindrical ½-cu. yd. steel skips which travel on bogies on a short length of rail-track in front of the mixer. The skips are lifted off the bogies by one of several travelling derrick cranes and discharged into mobile hoppers (*Fig. 3*). The hoppers are fixed to the top of a steel frame mounted on four casters so that it can be easily moved. The frame and hopper are lifted from one floor to another by crane.

### Party Walls.

The party walls, a detail of which is also shown in *Fig. 2*, are 8 in. thick and are cast between two 1-in. sheets of wood-wool. The reinforcement on each face

is generally  $\frac{1}{2}$ -in. bars at 12 in. centres vertically and  $\frac{3}{4}$ -in. bars at 12 in. centres horizontally. Additional horizontal bars are provided above openings in the walls. The walls were concreted in two lifts within panels of timber shuttering secured by patent cramps. The concrete is discharged directly into the shutters from three hoppers fixed in a steel frame (Fig. 4) which is placed by crane on the floor between two walls. Removable extensions on the chutes from the hoppers enable the concrete to be placed in the two lifts without altering the position of the hoppers. When one wall is concreted the chutes are reversed and the other wall is concreted without moving the frame. Horizontal and vertical gaps are left at intervals between the sheets of wood-wool (Fig. 5) so that the face of the concrete can be inspected after the shuttering has been removed.




Fig. 4.

#### Precast Stairs.

The main stairs are cast in situ, but others were precast on the site. Each flat is on two stories, access to the upper rooms being by means of a staircase of thirteen steps the flight being cast as one piece in a timber mould with the soffit uppermost. Eyes embedded in the casting enable it to be lifted by crane and

placed in position, where it is temporarily supported by a timber frame (Fig. 5) until the beam at the head of the flight has been cast.

The staircases for general use comprise two flights of eight steps each and a landing on each floor. The landing slabs are cast in situ, but the stairs are precast. Fig. 6 shows the method of retaining the bottom of the stairs by a 3-in. by 1 $\frac{1}{2}$ -in. steel channel grouted into holes in the walls of the stair well.




Fig. 3.



Fig. 5.

#### Boiler-house Floor.

The boiler house (Fig. 2) is entirely below ground. The reinforced concrete



# STEEL FORMS

**The multiple system of Steel Shuttering  
for in-situ concrete construction**

**STEEL FORMS** are being used on many important Contracts, Power Stations, Flats, Reservoirs, and were also used in the constructions of the Festival of Britain Exhibition.

**THE OUTSTANDING FEATURES** are speedy erection with safety—time and labour saving—easily handled and erected—every unit interchangeable—long life with low upkeep—first-class design and construction—overcomes timber wastage—repetition construction simplified—minimum cost with maximum efficiency—smooth, accurate concrete surfaces.

*Specifications and Quotations  
on request*

**A. A. BYRD & CO., LIMITED**

**210, Terminal House, Grosvenor Gardens, London, S.W.1.**

\*Phone: SLOane 5236.

\*Grams: Byrdicom, Wesphone, London.



## *-there's SGB again!*

Here, there and everywhere you see the sign of SGB—the efficient SCAFFOLDING SERVICE that saves time, money and labour throughout the country. Give SGB your SCAFFOLDING problems. Write or 'phone for details—

### **SCAFFOLDING (GREAT BRITAIN) LIMITED**

MITCHAM • SURREY

Telephone: MITCHAM 3400 (18 lines)    Telegrams: SCAFCO, MITCHAM

Branches at: ABERDEEN • BIRMINGHAM • BOURNEMOUTH • BRIGHTON  
BRISTOL • CAMBRIDGE • CARDIFF • DOVER • DUBLIN • DUNDEE  
EDINBURGH • EXETER • GLASGOW • HULL • LEEDS  
LIVERPOOL • MANCHESTER • NEWCASTLE • NOTTINGHAM • OXFORD  
PLYMOUTH • PORTSMOUTH • SOUTHAMPTON • STOKE-ON-TRENT • SWANSEA



*—the originators of tubular scaffolding!*




Fig. 6.—Details of Precast Stairs.

retaining wall is 2 ft. to 3 ft. thick and about 15 ft. high ; it is not waterproofed. On the inner side there is a  $4\frac{1}{2}$ -in. brick lining separated from the concrete by a  $4\frac{1}{2}$ -in. cavity. The construction of the floor (Fig. 7) allows for the drainage of any moisture that may seep through the concrete wall and trickle down the cavity.

The floor comprises a 9-in. slab of 1 : 8 concrete on the ground or on the base of the retaining wall, 18-in. triangular precast slabs covered with bituminous felt, a 6-in. reinforced concrete slab of 1 : 2 : 4 concrete, and  $1\frac{1}{2}$ -in. finish. The precast slabs (Fig. 7) are generally  $1\frac{1}{2}$  in. thick but have pads at each corner so that they





Fig. 7.—Floor of Boiler House.



No timber is required, no carpenters' workshop on site. No obstruction beneath. For solid Concrete or Hollow Tile floor and roof construction. Instantly-adjustable up to 15 ft., adaptable for larger spans. Invaluable also for repair work. On hire from stock. Write or 'phone.

**TRIANCO LTD. (D. 26)**  
Imber Court, East Molesey, Surrey  
'Phone: Emberbrook 3300 (4 lines)

stand clear of the 9-in. slab and form a series of horizontal channels having direct connection to the bottom of the cavity in the wall and draining to a sump.

The architects are Messrs. James & Bywaters, and the consulting civil engineers Messrs. R. T. James & Partners. The contractors are Messrs. Wm. Moss & Sons, Ltd.

### Change of Address.

Mr. R. F. Galbraith, B.Sc., consulting engineer, has removed to 9 Southampton Place, London, W.C.1. (Telephone: Chancery 2067).

### Specialties Allied to—

#### **CONCRETE & BUILDING PRODUCTS**

Including Accelerators, Retarders, Hardeners, Waterproofers, Oilproofers, Cement Paints, etc.

For full particulars please write

#### **ALLIED BUILDING COMMODITIES**

LITTLE ROYD, HUDDERSFIELD.



## **AQUAREP**

SEND FOR  
DETAILS

for 100%  
**WATERPROOF  
CONCRETE**

### **DAMP-PROOFING LTD.**


DEPTFORD Tel. TIDaway 1484-7 LONDON, S.E.

August, 1951.

# 'RITECURE'

## membrane curing

### for concrete runways roads · floors & walls



"Ritecure" membrane curing material forms a cellophane-like skin on the surface of the concrete. Since it is applied before the setting of the cement has taken place, it ensures retention of the maximum amount of moisture in the concrete, eliminating hair and wind cracking caused by too rapid drying out of the cement in the face of the concrete immediately after laying. It is not affected by the heat of the sun and, while it is not sold as an anti-frost mixture, since "Ritecure" itself will not freeze, it gives protection against 5-10° of frost.

This one-man operation of curing concrete—horizontal or vertical surfaces—has brought concrete curing to a simple, speedy and economical process, whereby the highest degree of curing efficiency is obtained without the use of costly covering materials and their heavy handling charges. It is easily applied through a spray, and various sizes of equipment are available for small or large areas. "Ritecure" is in use in temperatures of extreme degrees all over the world, and is being extensively used by leading Engineers and Contractors in this country for concrete runways, roads, and other forms of concrete work.


"Ritecure" is backed by a highly developed Technical Service with an extensive experience in concrete curing, so that its correct and economical use is assured on all forms of concrete work.

The illustration above shows its application in this country at a large aerodrome where 7½ acres of concrete were laid and cured with "Ritecure".

Fully illustrated details and technical information are available on application to:

**STUART B. DICKENS**

36 VICTORIA STREET, LONDON, S.W.1  
OLD MILTON STREET, LEICESTER (Works)



A general view of the new coking plant at the East Greenwich Gasworks, designed and constructed by Messrs. Simon-Carves, Ltd., for the South Eastern Gas Board. All the structures shown are supported on Simplex Concrete Cast-in-Situ Piles.

## **SIMPLEX CONCRETE PILES LTD.**

25 BRECHIN PLACE,

SOUTH KENSINGTON,

LONDON, S.W.7

Telephone: Fremantle 0035-6

---



## A Prestressed Concrete Lighthouse.

THE Berck lighthouse near Boulogne has been reconstructed in prestressed concrete (Fig. 1). The structure is 131 ft. 3 in. high to the focal plane, and the shaft is a true cylinder of 18 ft. 4½ in. external diameter.

The cast-in-situ concrete plinth extends 18 ft. 6 in. above the ground and has an external diameter of 20 ft., the wall being 1 ft. 6 in. thick. Thirty-six prestressing cables of eighteen wires each (Figs. 1 and 2) extend from the top of the plinth into the foundation, where they are

anchored by a U-bend. The tops of these cables are anchored in cones as shown in Fig. 2.

The shaft is 106 ft. 3 in. high above the plinth and is constructed of precast concrete segments, which are generally not reinforced and are 7 in. thick, 13½ in. high, and 19 in. long (measured around the circumference). There are thirty-six segments in one course. Special segments are provided at windows and to contain the prestressing cables in the shaft. There are four sets of nine vertical




Fig. 1.

cables in the shaft, each cable comprising twelve wires (Fig. 2) and extending 10 ft. 8 in. into the plinth. Each set of cables ends at a different height above the plinth as shown in Fig. 1. A precast prestressed concrete ring, 4 in. thick, 18 ft. 4½ in. external diameter, and 8 in. wide, is provided between every third

which the wires pass, were arranged in a circle. At each block a screw-jack was placed radially to bear against a piece of timber between the block and the jack. The jacks stretched the wires and concrete was placed between the blocks. When the concrete had hardened, the jacks were released and the concrete ring




Fig. 2.—Details of Anchorage.




Fig. 3.—Precasting the Prestressed Rings.

course of segments. The segments and rings are set in cement mortar. The wires in the cables are 0.2 in. diameter, and the cables are stretched in situ and anchored in accordance with the Freyssinet system. The rings are prestressed with 0.1-in. wires bonded to the concrete, and were cast as shown in Fig. 3. A central circular buttress was constructed and precast rectangular concrete blocks, through

was compressed circumferentially. Holes through the blocks permit the passage of the vertical cables after erection of the rings.

The internal reinforced concrete staircase was constructed at the same time as the wall, and the four columns supporting the stairs were used temporarily to support a working platform. These notes and illustrations are from "Travaux."



DELIVERED DIRECT TO ANY  
CONTRACT BY MOTOR LORRY.

Quotations on Application.

Telephone : Paddington 2024 (3 lines).

WASHED  
**BALLAST, SAND, SHINGLE &**  
Crushed Aggregate for Reinforced Concrete.

**WILLIAM BOYER & SONS, LTD.**

*Sand and Ballast Specialists,*

**IRONGATE WHARF,  
PADDINGTON BASIN, W.**

MEMBERS OF B.S. & A.T.A.

WINGET TECHNIQUES IN CONCRETE PRODUCTION

# Speedy compaction of concrete to maximum density

*by the Winget "Vibrocon" Vibrating Spade*

In 30 seconds the 'Winget "Vibrocon" spade will give maximum compaction of the new, dry, mixes. The 70 m.m. ( $2\frac{1}{2}$ ") diameter is used for mass concrete and the 55 m.m. ( $2\frac{1}{10}$ ") for work including closer reinforcement on smaller sections. Both

sizes give a high-frequency vibration of 9,000 impulses/minute with engine and transmission rate only 3,000 R.P.M. There are no gears or belts, and handling is simple. There is a choice of 3 drives—petrol, electric or air power units.



*Winget "Vibrocon" in use in the manufacture of concrete piles*



The Winget "Vibrocon" Vibrating Spade ensures all these important requirements for successful vibration of concrete:— increased strength, less shrinkage, greater density and homogeneity; greater resistance to frost; better bond between concrete and reinforcement; better bond at construction joints; economy of materials.

*Ask for No. 127 and other Winget Publications on concrete mixing, placing, batching, etc.*



## Winget

CONCRETE PLANT SPECIALISTS

WINGET LTD ROCHESTER  
KENT ENGLAND

Tel: Strood 7276 (5 lines). Telegrams: Wingetiam Rochester

## MISCELLANEOUS ADVERTISEMENTS.

*Situations Wanted, 3d. a word: minimum 7s. 6d. Situations Vacant, 4d. a word: minimum 10s. Other miscellaneous advertisements, 4d. a word: 10s. minimum. Box number 1s. extra.*

**Advertisements must reach this office by the 23rd of the month preceding publication.**

## SITUATIONS VACANT.

**SITUATION VACANT.** A well-known firm of heavy industrial plant engineers, situated near Manchester, requires a reinforced concrete designing engineer with experience in all types of industrial structures. The position is a permanent one and progressive. A pension fund is in operation. Five-day week. The commencing salary will be between £800 and £1,000 a year according to ability. Apply briefly stating previous employers, with dates and positions held, to Box 2476, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1, and quoting reference PE/707.

**SITUATION VACANT.** Required. Works manager who has had several years' experience in precast concrete work. This is a permanent post in the London area. Please write giving full details of age, salary expected, length of service, and previous employers. Those without experience will not be considered. Box 2480, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Assistant architect required in the Architectural Section of Imperial Chemical Industries Limited, General Chemicals Division, Chief Engineer's Department, Runcorn, and applicants should have had good experience in design and preparation of working drawings. Other factors being equal, preference will be given to those who have passed the final examination of the R.I.B.A. Salary dependent on age and experience. Pension fund membership. Apply in writing, quoting E/64, to STAFF MANAGER, IMPERIAL CHEMICAL INDUSTRIES LIMITED, GENERAL CHEMICALS DIVISION, CUNARD BUILDING, LIVERPOOL, 3, giving details in support of application.

**SITUATION VACANT.** Reinforced concrete senior designer experienced in shell construction required for London office. Salary £1,000 per year upwards, according to experience. Write Box K.202, c/o STREETS, 110 Old Broad Street, London, E.C.2.

**SITUATIONS VACANT.** Permanent posts are offered to draughtsmen and draughtsmen-detailers by a London firm of reinforced concrete engineers. It is essential that the applicants have a knowledge of reinforced concrete. A superannuation scheme is in operation, and the salaries offered are between £400 and £600 per annum, according to qualifications. Write, giving full details, to Box C.E.995, at 191 Gresham House, London, E.C.2.

**SITUATIONS VACANT.** Simon-Carves, Ltd., require senior draughtsmen experienced in mechanical or structural engineering. Experience in any of the following is desirable but not essential: chemical engineering plant, pipework or pressure vessels, colliery surface plant, structural steelwork, and coal-washing plant. Applications, quoting PE/710, and giving details of age, qualifications, and experience, to the PERSONNEL MANAGER, SIMON-CARVES, LTD., Bird Hall Lane, Cheadle Heath, Stockport.

**SITUATIONS VACANT.** Well-known engineering company in the Manchester area has vacancies for competent mechanical and structural engineering draughtsmen in the following categories: (a) Section leaders. (b) Senior draughtsmen. (c) Junior draughtsmen. Experience in conveying and coal-washing plants desirable but not essential. Salaries for draughtsmen will be up to £600 per year, according to age and experience. Pension scheme in operation. Apply, giving full particulars of experience, age, etc., and quoting A/8, to Box 2481, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Designer/draughtsman required for London head office and/or site offices of old-established firm of reinforced concrete engineers specialising in hollow tile type floor construction. Progressive post. Write fully qualifications, and salary required. Box 2483, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Detailer/draughtsman to specialise in the design of reinforced concrete floors and roofs required for Bristol office of large London company. Write stating age, experience, and salary required. Box C.E.120, at 191 Gresham House, London, E.C.2.

**SITUATION VACANT.** A permanent post is offered to an active structural or civil engineer as service inspector. Considerable experience in responsible supervising capacity in the erection of reinforced concrete structures, with some design experience, is required. Prepared to travel extensively in the British Isles, but must be resident in the London area. Attributes required are agreeable personality, sound judgement on erection problems, and able to write concise factual reports. Salary £800 with expenses. Write, giving full details, to Box C.E.119, at 191 Gresham House, London, E.C.2.

**SITUATION VACANT.** Draughtsman accustomed to taking site dimensions and setting-out required by old-established London tiling and terrazzo contractors. Permanent position. Write fully experience, and salary required. Box 2485, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Qualified and experienced mechanical engineer required by well-known London engineering firm for their development department. Drawing office experience essential and some knowledge of structural engineering an advantage. Only men with considerable drive, initiative, and the will to carry schemes through to finality need apply. Write, giving fullest information, to MANAGING DIRECTOR, ACROW (Engineers), LTD., South Wharf, Paddington, London, W.2.

**SITUATIONS VACANT.** Civil and structural designer-draughtsmen are required by Imperial Chemical Industries Limited, General Chemicals Division, to assist in the design of steel and/or reinforced concrete structures for chemical plants. Salary dependent on age and experience. Pension fund membership. Runcorn area. Apply in writing, quoting E/67, to STAFF MANAGER, IMPERIAL CHEMICAL INDUSTRIES LIMITED, GENERAL CHEMICALS DIVISION, CUNARD BUILDING, LIVERPOOL, 3, giving details in support of application.

**SITUATION VACANT.** Wanted for consulting structural engineer's office, senior draughtsman with good experience in all branches of reinforced concrete. Experience in structural steelwork an advantage. Salary according to age and experience. Please apply in writing to F. J. SAMUELY, 8 Hamilton Place, London, W.1.

**SITUATION VACANT.** Reinforced concrete draughtsman wanted by consultants in North Herts. Apply stating age, experience and salary required. Box 2486, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Applications are invited from men having training and experience in civil engineering and structural drafting for positions in New Zealand as draughtsmen with the New Zealand Ministry of Works. Salaries offered will be based on qualifications and experience, and positions up to £816 10s. N.Z. per annum are available. Men with eight to twelve years' experience are preferred. Further information, conditions of appointment, and application forms are obtainable from THE HIGH COMMISSIONER FOR NEW ZEALAND, 415 Strand, London, W.C.2, with whom completed applications in duplicate (accompanied by copies only of two recent personal references) should be lodged not later than 20 August, 1951.

**SITUATION VACANT.** Dow-Mac (Products) Limited require assistant chief designer for precast and prestressed concrete. Design ability required to B.Sc., or equivalent standard. Previous experience in precast concrete essential, including design of moulds and estimating. Several years' experience in engineering other than precast concrete required. Minimum age 35. Must be capable of carrying on all design and estimating in absence of chief and ensuring smooth continuity of work within the organisation of the factory and associated companies. Salary according to age and experience, but not less than £750 per annum. Apply in writing in the first place to the SECRETARY, DOW-MAC (PRODUCTS) LIMITED, Tallington, Stamford, Lincoln.

**SITUATION VACANT.** Reinforced concrete designer required for responsible position to take charge of drawing office with consulting engineers in South Wales. Please state age, experience, and salary required. Box 2493, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Wanted. Draughtsman to detail large frame construction in precast reinforced concrete. Position would suit a good architectural or engineering assistant with some sound experience. A permanent interesting position to the right man. Apply stating age, experience, and salary required. Box 2490, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

(Continued on facing page.)

**MISCELLANEOUS ADVERTISEMENTS**

(Continued from page 111.)

**SITUATION VACANT.** Dow-Mac (Products) Limited require estimating assistant for precast and prestressed concrete. Experience in prestressed work not essential, but several years in precast essential, as applicant will be required to complete estimates, including mould pricing, with minimum supervision by senior estimator. Preference will be given to an applicant with some experience as draughtsman and capable of giving maximum assistance in office engaged on a wide variety of work. Age about 24 to 28. Salary according to age and experience, but not less than £375. Apply in writing, in the first place, to the SECRETARY, DOW-MAC (PRODUCTS) LIMITED, Tallington, Stamford, Lincs.

**SITUATIONS VACANT.** COMMONWEALTH OF AUSTRALIA, DEPARTMENT OF WORKS AND HOUSING. ENGINEERS are required for National Defence Projects and Development Works in all States of the Commonwealth and in New Guinea. Projects include—*Civil*: Hydro-electric, water supply and sewerage, roads, aerodromes, soil mechanics, timber, reinforced concrete and steel structures, including major Government buildings, wharves and harbour works. *Mechanical*: Diesel and steam power stations and pumping plants, services for buildings, including hospitals and Government establishments, heating, air-conditioning ventilation and refrigeration, earth-moving plant and motor repair workshops. *Electrical*: H.T. and L.T. reticulation, lighting for defence airports, services for hospitals and Government buildings. Salary between £62 and £1,286 per annum, according to academic qualifications and experience, with higher rates for personnel selected for more senior positions. Passages paid, but appointees required to remain in Commonwealth Service for three years. Excellent prospect of further period if service is satisfactory, and permanent appointment may be offered to suitable persons. Splendid opportunity for single men. Houses will be available for married men within reasonable period after arrival. Technical officers from Australia will interview during August. Applications to be addressed to THE PUBLIC SERVICE BOARD REPRESENTATIVE, Australia House, The Strand, London, W.C.2.

**SITUATION VACANT.** Designer-draughtsman with experience of reinforced concrete industrial structures required by consulting engineers in Bayswater. Permanent position, good salary, and prospects. Apply with full details, to Box 2492, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Resident engineer required for Pakistan. Commencing on two years' agreement. Large reinforced concrete industrial works. Write stating age, experience, and salary required, to CLARKE, NICHOLLS AND MARCEL (Consulting Engineers), 21 Westbourne Grove, London, W.2.

**SITUATIONS VACANT.** Applications are invited to fill vacancies at Edinburgh for structural engineering designer-draughtsmen. Applicants should be quick and accurate detailers with a thorough knowledge of general structural design, building construction, and structural surveying. A good knowledge of structural steelwork and/or reinforced concrete is also necessary. Salary on range £330 to £560 with entry up to £466 per annum according to age, qualifications, and experience. Apply in writing stating age and giving details of training and experience, to the SECRETARY, MINISTRY OF WORKS, 122 George Street, Edinburgh, 2.

**SITUATION WANTED.**

**SITUATION WANTED.** Young, capable, energetic South African structural engineer, B.Sc. (Rand), with 4½ years' extensive reinforced concrete experience, seeks position with leading progressive construction company employing up-to-date methods and techniques. Available for personal interview after August 14. Box 2480, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.


**FOR SALE.**

**FOR SALE.** New 2½-in. bore rubberised canvas suction hose with coiled rust-proofed wire insert in 12 ft. and 6 ft. lengths. 10s. and 5s. per length, carr. paid. Small orders C.W.O. please. WOODFIELD & TURNER, Burnley. Telephone: Burnley 3065.

**FOR SALE.** Sacks, bags, and curing cloths for sale. You want the best type and quickest delivery. Write JOHN BRAYDON, LTD., 26 The Highway, London, E.1. Telephone: ROYAL 1044.

**Construction work in the  
Belgian Congo.**

THE Societe des Forces Hydro-electriques du Bas-Congo (30 rue Marie de Bourgogne, Brussels, Belgium) wishes to receive tenders for construction work in connection with hydro-electric schemes at Zongo and Tshopo in the Belgian Congo. Information on the work will be sent on request to firms interested, and tender forms will be available later.



**Trent Gravels**

**10,000 tons per week**

Washed & Crushed 1½ in. to ¾ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

**TRENT GRAVELS LTD**

ATTENBOROUGH

NOTTS

Telephone: Beeston 54255.





# DATA FOR PRICING REINFORCED CONCRETE.

## Materials.

(Delivered in London area.)

**AGGREGATES** (per cu. yd.).—Washed sand, 17s.  
Clean shingle:  $\frac{1}{2}$  in., 15s. 2d.;  $\frac{3}{4}$  in., 17s. 6d.  
Thames ballast, 15s. 9d.  
**CEMENT** (per ton, delivered at Charing Cross).—  
Portland cement, 6 tons and upwards, 93s. 9d.  
1 ton to 6 tons, 98s. 9d. Paper bags and  
non-returnable jute sacks included.  
Rapid-hardening Portland, 6s. above ordinary  
Portland.  
Aquacrete and 417, 32s. 6d. above ordinary  
Portland; paper bags included.  
Colorcrete (buff, red, and khaki), in 6-ton loads,  
135s. 3d.; paper bags included.  
Snowcrete, £12 11s. 3d., inc. paper bags.  
"Super-Cement," 32s. 6d. per ton above ordi-  
nary Portland cement; paper bags included.  
High-alumina cement, 1 ton and upwards,  
255s. per ton; paper bags 22s. per ton  
extra.  
Snowcem paint, 56s. per cwt. inc. containers.  
**SHUTTERING**.—For prices of timber, refer to S.R. &  
O., 1949, No. 1079 (price 1s. 1d.) and No. 94  
(price 5d.) issued by H.M. Stationery Office.  
**REINFORCEMENT**.—Mild steel round bars (per  
cwt.):  $\frac{1}{2}$  in. to 2 $\frac{1}{2}$  in., 28s. 2d.  $\frac{3}{4}$  in. to  
 $\frac{1}{2}$  in., 29s.  $\frac{1}{2}$  in., 29s. 8d.  $\frac{3}{4}$  in., 31s.

## Materials and Labour.

(Contracts up to £5000. Inc. 10 per cent. profit.)

**PORTLAND CEMENT CONCRETE, 1 : 2 : 4**.—  
Foundations, 2s. 2d. per cu. ft. Columns, 2s. 5d.  
per cu. ft. Beams, 2s. 5d. per cu. ft. Floor  
slabs 4 in. thick, 6s. 10d. per sq. yd.; Do.,  
5 in., 8s. 7d.; Do., 6 in., 10s. 3d.; Do., 7 in.,  
12s. Walls 6 in. thick, 10s. 3d. per sq. yd.  
Add for hoisting 3s. 6d. per cu. yd. above  
ground floor level. Add for rapid-hardening  
Portland cement 2s. per cu. yd.  
**REINFORCEMENT**.—Mild steel round bars, includ-  
ing cutting, bending, fixing, and wire (per  
cwt.)— $\frac{1}{2}$  in. to  $\frac{3}{4}$  in., 48s. 6d.  $\frac{1}{2}$  in. to  $\frac{1}{2}$  in.,  
43s. 6d.  $\frac{3}{4}$  in. to 2 $\frac{1}{2}$  in., 42s.  
**SHUTTERING AND SUPPORTS**.—  
Walls, 155s. per square.  
Floors (average 10 ft. high), 160s. per square.  
In small quantities, 1s. 8d. per sq. ft.  
Columns, average 18 in. by 18 in. (per sq. ft.),  
1s. 8d.; in narrow widths, 2s.  
Beam sides and soffits, average 9 in. by 12 in.  
(per sq. ft.), 2s.; in narrow widths, 2s. 2d.  
Raking, cutting, and waste, 5d. per lin. ft.  
Labour on splays, 3d. per lin. ft.  
Small fillets to form chamfers, 6d. per lin. ft.


## Wages.

The rates of wages on which the above prices  
are based are: Carpenters and joiners, 3s.  
per hour (carpenters 2d. a day tool money);  
Labourers, 2s. 6d.; Men on mixers and  
hoists, 2s. 7d.; Bar-benders, 2s. 8d.

This column is specially compiled for "Concrete and  
Constructional Engineering," and is strictly copyright.

## CONCRETE

DEFINITELY GIVES YOU  
**STRENGTH** CONCRETE



**JOHNSON** AVOIDS  
segregation  
**'MAXIBRATER'**  
VERTICAL VIBRATION

Cruciform design of table top ensures equal vibra-  
tion over whole area. Rugged construction for long  
and continuous service with minimum upkeep costs.  
Ave. compressive strength 6,000 lb. per sq.  
in. in weekly independent tests over 12 months.  
Takes any precast work up to 10 ft. lengths.  
See Folder X/24.

**JOHNSON "MIXRITE"**  
**5/3 $\frac{1}{2}$  Concrete Mixer**

**QUICK to REPAY**

**INITIAL  
OUTLAY**

**Continuous  
OUTPUT  
20/30  
cu. yds.**

**per DAY.**



Completely enclosed all-steel machine cut internal gear  
and pinion (inspection cover). Non-rusting hand wheel.  
Fully accessible engine housing. Power unit, 1 $\frac{1}{2}$  h.p. Petter  
air-cooled, or Lister water-cooled. Diesel radiator cooled.  
Electric motor drive if required. All gears totally enclosed.  
Weight, 9 $\frac{1}{2}$  cwt. Width, 2 ft. 8 in. Length, 6 ft. Height,  
5 ft. 2 in. to 5 ft. 6 in. Discharge, 2 ft. 6 in.  
Easy loading and discharge. Mixing Drum (heavy  
cast iron base, heavy gauge cone) pivots through 360 deg.  
Mobile model "MIXRITE" Trailer type also available.  
Write for Folder MX/24.

• May we send you full details of

JOHNSON CONCRETE VIBRATING MACHINES: Tables, Internal  
Vibrators, Platform Vibrators, Screened Units for better concrete  
road-making. WRITE TODAY. TERMS CAN BE ARRANGED.

**G. H. JOHNSON (MACHINERY)  
LTD.**  
X/MX/24, ADSWOOD RD., STOCKPORT

or contact our nearest representative:

LONDON: Prospect 7871. BRISTOL and SOUTH WALES: (Bristol)  
Lobgate 277. MIDLANDS: 49 Omar Road, Stoke, Coventry.  
LANCASHIRE: Gaitley 4404. YORK, NORTHUMBRIA and  
DURHAM: Otley 2463. NORTH WALES and SHROPSHIRE:  
Chester 22037. SCOTLAND: 143 Hillside Road, Mansewood,  
Glasgow.





## SULPHATE-RESISTING PORTLAND CEMENT

This Blue Circle Product has been specially introduced for concrete which is subject to the destructive action of soluble sulphates, e.g. in sea water, some ground waters and certain clay soils. Provided due regard is paid to producing good dense concrete, Sulphate-Resisting Cement will make it proof against concentrations of up to 2 per cent. sulphur trioxide in soil and up to 500 parts per 100,000 in water (0.5%)

### **S.R.P.C. POSSESSES ALL THE DURABILITIES AND STRENGTH CHARACTERISTICS OF PORTLAND CEMENT**

*A satisfactory interim report has been received from the Director, Building Research Station. Copies of the Summary of this interim report will be forwarded on application.*



**THE CEMENT MARKETING CO. LTD**

PORTLAND HOUSE · TOTHILL STREET · LONDON · SW1

or G. & T. Earle Ltd · Wilmington · Hull

The South Wales Portland Cement & Lime Co. Ltd. Penarth. Glam



Every  
well-planned road  
laid in  
**Reinforced Concrete**  
is a step nearer  
to national  
highway perfection

**BRC**

REINFORCEMENT FOR ROADS

**THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD**

*London, Birmingham, Bristol, Leeds, Leicester, Manchester, Newcastle, Sheffield, Cardiff, Glasgow,  
Dublin, Belfast*

M-W.596